

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401600443

Receive Date:

04/09/2018

Report taken by:

## Site Investigation and Remediation Workplan (Initial Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Refer to Rules 340, 905, 906, 907, 908, 909, and 910

### OPERATOR INFORMATION

Name of Operator: <u>PDC ENERGY INC</u>	Operator No: <u>69175</u>	<b>Phone Numbers</b>
Address: <u>1775 SHERMAN STREET - STE 3000</u>		Phone: <u>(303) 860-5800</u>
City: <u>DENVER</u>	State: <u>CO</u>	Zip: <u>80203</u>
Contact Person: <u>Karen Olson</u>	Email: <u>Karen.Olson@pdce.com</u>	Mobile: <u>( )</u>

### PROJECT, PURPOSE & SITE INFORMATION

#### PROJECT INFORMATION

Remediation Project #: \_\_\_\_\_ Initial Form 27 Document #: 401600443

#### PURPOSE INFORMATION

- |  |  |
|--|--|
| <input type="checkbox"/> 901.e. Sensitive Area Determination                                       | <input type="checkbox"/> 909.c.(5), Rule 910.b.(4): Remediation of impacted ground water                   |
| <input checked="" type="checkbox"/> 909.c.(1), Rule 905: Pit or PW vessel closure                  | <input type="checkbox"/> Rule 909.e.(2)A.: Notice completion of remediation in accordance with Rule 909.b. |
| <input checked="" type="checkbox"/> 909.c.(2), Rule 906: Spill/Release Remediation                 | <input type="checkbox"/> Rule 909.e.(2)B.: Closure of remediation project                                  |
| <input type="checkbox"/> 909.c.(3), Rule 907.e.: Land treatment of oily waste                      | <input type="checkbox"/> Rule 906.c.: Director request   |
| <input type="checkbox"/> 909.c.(4), Rule 908.g.: Centralized E&P Waste Management Facility closure | <input type="checkbox"/> Other _____   |

#### SITE INFORMATION

N Multiple Facilities ( in accordance with Rule 909.c. )

Facility Type: <u>LOCATION</u>	Facility ID: <u>319532</u>	API #: _____	County Name: <u>WELD</u>
Facility Name: <u>SITZMAN-65N65W 27NWSW</u>		Latitude: <u>40.368575</u>	Longitude: <u>-104.656508</u>
		** correct Lat/Long if needed: Latitude: <u>40.369520</u>	Longitude: <u>-104.657630</u>
QtrQtr: <u>NWSW</u>	Sec: <u>27</u>	Twp: <u>5N</u>	Range: <u>65W</u>
		Meridian: <u>6</u>	Sensitive Area? <u>Yes</u>

#### SITE CONDITIONS

General soil type - USCS Classifications SM Most Sensitive Adjacent Land Use Residential

Is domestic water well within 1/4 mile? Yes Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? Yes

#### Other Potential Receptors within 1/4 mile

A water well is located approximately 125 feet northwest of the location. Occupied housing is located approximately 270 northwest of the location.

# SITE INVESTIGATION PLAN

## TYPE OF WASTE:

- ☒ E&P Waste      ☐ Other E&P Waste      ☐ Non-E&P Waste
- ☒ Produced Water      ☐ Workover Fluids
- ☐ Oil      ☐ Tank Bottoms
- ☐ Condensate      ☐ Pigging Waste
- ☐ Drilling Fluids      ☐ Rig Wash
- ☐ Drill Cuttings      ☐ Spent Filters
- ☐ Pit Bottoms
- ☐ Other (as described by EPA)

## DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
UNDETERMINED	GROUNDWATER	Undetermined.	Completion of Site Investigation.
Yes	SOILS	Vertical defined; lateral undefined	Refer to Figure 1.

## INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

On March 9, 2018, historic petroleum hydrocarbon impacts were discovered below the produced water vessel during plug and abandonment activities at the Sitzman 1U tank battery. Excavation activities were subsequently initiated below the former production tanks. Between March 9 and March 13, 2018, approximately 340 cubic yards of impacted material were removed and transported to the North Weld Waste Management Facility in Ault, Colorado for disposal under PDC waste manifests. Four (4) soil samples (SS01 - SS04) were collected during the initial site investigation at depths ranging between 10 and 18 feet below ground surface (bgs) and submitted to Summit Scientific Laboratories (Summit) for analysis of benzene, toluene, ethylbenzene, total xylenes (BTEX), naphthalene, total petroleum hydrocarbons (TPH) – gasoline range organics (GRO) by United States Environmental Protection Agency (USEPA) Method 8260, and TPH – diesel range organics (DRO) by USEPA Method 8015. Analytical results indicated TPH concentrations were above the applicable COGCC Table 910-1 soil standards in soil samples SS01, SS03, and SS04. The excavation extent and soil sample locations are illustrated on Figure 1. Soil analytical data is summarized in Table 1 and laboratory reports are provided in Attachment A.

## PROPOSED SAMPLING PLAN

### Proposed Soil Sampling

☐ Will soil samples be collected as part of this investigation? ( Number, type (grab/composite), analyses, and locations of samples ):

### Proposed Groundwater Sampling

☐ Will groundwater samples be collected as part of this investigation? ( Number, analyses, and locations of samples ):

### Proposed Surface Water Sampling

☐ Will surface water samples be collected as part of this investigation? ( Number, analyses, and locations of samples ):

## Additional Investigative Actions

☒ Additional alternative investigative actions described in attached Site Investigation Plan ( summary ):

The lateral extent of remaining hydrocarbon impacts in soil has not been defined. Investigation and delineation activities will be conducted concurrent with the proposed remediation plan.

# SITE INVESTIGATION REPORT

## SAMPLE SUMMARY

### Soil

Number of soil samples collected 4

Number of soil samples exceeding 910-1 3

Was the areal and vertical extent of soil contamination delineated? No

Approximate areal extent (square feet) 3000

### NA / ND

-- Highest concentration of TPH (mg/kg) 6600

NA Highest concentration of SAR

BTEX > 910-1 No

Vertical Extent > 910-1 (in feet) 18

### Groundwater

Number of groundwater samples collected 0

Was extent of groundwater contaminated delineated? No

Depth to groundwater (below ground surface, in feet)

Number of groundwater monitoring wells installed

Number of groundwater samples exceeding 910-1

Highest concentration of Benzene (µg/l)

Highest concentration of Toluene (µg/l)

Highest concentration of Ethylbenzene (µg/l)

Highest concentration of Xylene (µg/l)

Highest concentration of Methane (mg/l)

### Surface Water

0 Number of surface water samples collected

Number of surface water samples exceeding 910-1

If surface water is impacted, other agency notification may be required.

## OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☐ Were background samples collected as part of this site investigation?

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards)

Volume of liquid waste (barrels)

☒ Is further site investigation required?

Delineation of remaining petroleum hydrocarbon impacts in soil is required and will be conducted during remediation activities. In addition, groundwater conditions on site must be assessed.

# REMEDIAL ACTION PLAN

## SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Between March 9 and March 13, 2018, approximately 340 cubic yards of impacted material were removed and transported to the North Weld Waste Management Facility in Ault, Colorado for disposal under PDC waste manifests. Remaining impacted material will be treated on-site using ex-situ chemical oxidation.

## REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Excavation and ex-situ chemical oxidation will be conducted to address remaining petroleum hydrocarbon impacts in soil. Confirmation soil samples will be collected for every 100 cubic yards of soil treated with hydrogen peroxide to confirm hydrocarbon concentrations were reduced below COGCC Table 910-1 soil standards and material could be used for backfilling. Soil samples will be collected from the sidewalls of the final excavation extent prior to backfilling. In addition, a groundwater sample will be collected from the excavation area prior to backfilling. A summary of remediation and sampling activities will be provided in a supplemental report.

## Soil Remediation Summary

☐ In Situ

\_\_\_\_\_ Bioremediation ( or enhanced bioremediation )

\_\_\_\_\_ Chemical oxidation

\_\_\_\_\_ Air sparge / Soil vapor extraction

\_\_\_\_\_ Natural Attenuation

\_\_\_\_\_ Other \_\_\_\_\_

☒ Ex Situ

Yes \_\_\_\_\_ Excavate and offsite disposal

\_\_\_\_\_ If Yes: Estimated Volume (Cubic Yards) \_\_\_\_\_ 340

\_\_\_\_\_ Name of Licensed Disposal Facility or COGCC Facility ID # \_\_\_\_\_

Yes \_\_\_\_\_ Excavate and onsite remediation

No \_\_\_\_\_ Land Treatment

No \_\_\_\_\_ Bioremediation (or enhanced bioremediation)

Yes \_\_\_\_\_ Chemical oxidation

No \_\_\_\_\_ Other \_\_\_\_\_

## Groundwater Remediation Summary

☐ \_\_\_\_\_ Bioremediation ( or enhanced bioremediation )

☐ \_\_\_\_\_ Chemical oxidation

☐ \_\_\_\_\_ Air sparge / Soil vapor extraction

☐ \_\_\_\_\_ Natural Attenuation

☐ \_\_\_\_\_ Other \_\_\_\_\_

## GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

Groundwater was encountered during initial site investigation activities at approximately 21 feet bgs. An excavation groundwater sample will be collected following the completion of remediation activities. A groundwater monitoring and remediation plan will be developed following the evaluation of groundwater analytical results.

## REMEDATION PROGRESS UPDATE

### PERIODIC REPORTING

**Frequency:** ☐ Quarterly ☐ Semi-Annually ☐ Annually ☐ Other \_\_\_\_\_

**Report Type:** ☐ Groundwater Monitoring ☐ Land Treatment Progress Report ☐ O&M Report  
☐ Other \_\_\_\_\_

### WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? Yes

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

No beneficial use.

Volume of E&P Waste (solid) in cubic yards 340

E&P waste (solid) description Petroleum hydrocarbon impacted soil.

COGCC Disposal Facility ID #, if applicable: \_\_\_\_\_

Non-COGCC Disposal Facility: North Weld Waste Management Facility

Volume of E&P Waste (liquid) in barrels 0

E&P waste (liquid) description \_\_\_\_\_

COGCC Disposal Facility ID #, if applicable: \_\_\_\_\_

Non-COGCC Disposal Facility: \_\_\_\_\_

## RECLAMATION PLAN

### RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

The excavation area will be backfilled and re-graded to match pre-existing conditions. The tank battery will not be reconstructed and the location will be reclaimed in accordance with COGCC Rule 1004.

Is the described reclamation complete? No

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☐ Interim? ☐ Final?

Did the Surface Owner approve the seed mix? \_\_\_\_\_

If NO, does the seed mix comply with local soil conservation district recommendations? \_\_\_\_\_

## IMPLEMENTATION SCHEDULE

### PRIOR DATES

Date of Surface Owner notification/consultation, if required. \_\_\_\_\_

Actual Spill or Release date, if known. \_\_\_\_\_

### SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). 03/09/2018

Date of commencement of Site Investigation. 03/09/2018

Date of completion of Site Investigation. \_\_\_\_\_

### REMEDIAL ACTION DATES

Date of commencement of Remediation. 03/09/2018

Date of completion of Remediation. \_\_\_\_\_

### SITE RECLAMATION DATES

Date of commencement of Reclamation. \_\_\_\_\_

Date of completion of Reclamation. \_\_\_\_\_

### OPERATOR COMMENT

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Karen Olson

Title: Senior EHS Manager

Submit Date: 04/09/2018

Email: Karen.Olson@pdce.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_

Date: \_\_\_\_\_

Remediation Project Number: \_\_\_\_\_

### COA Type

### Description

--	--

### Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

#### Att Doc Num

#### Name

401600443	FORM 27-INITIAL-SUBMITTED
401600690	SITE MAP
401600691	ANALYTICAL RESULTS

Total Attach: 3 Files

### General Comments

#### User Group

#### Comment

#### Comment Date

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)