



Well Summary Report

(Unknown) Porter 3 3/20/2018 06:00 - 3/21/2018 06:00

API 05-123-05167	State/Province Colorado	County Weld	Field Name Non-Operated	Well Status	Total Depth (ftKB)	Primary Job Type Abandon Well
---------------------	----------------------------	----------------	----------------------------	-------------	--------------------	----------------------------------

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	7.00	13:00	inactive	inactive		
13:00	2.00	15:00	IWHD	Install Wellhead	Dig Up WH, cut CSG top, CSG top OD measured 10 5/8", weld on 10 3/4" slip collar to CSG top, weld on 10 3/4" by 11" 3K WH flange. Install Cellar ring, backfill hole	
15:00	15.00	06:00	inactive	inactive		

(Unknown) Porter 3 3/22/2018 06:00 - 3/23/2018 06:00

API 05-123-05167	State/Province Colorado	County Weld	Field Name Non-Operated	Well Status	Total Depth (ftKB)	Primary Job Type Abandon Well
---------------------	----------------------------	----------------	----------------------------	-------------	--------------------	----------------------------------

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	8.00	14:00	inactive	inactive		
14:00	3.00	17:00	SRIG	Rig Up/Down	MIRU Ensign Rig #312 & Equipment	
17:00	1.00	18:00	CTRL	Crew Travel		
18:00	12.00	06:00	inactive	inactive		

(Unknown) Porter 3 3/23/2018 06:00 - 3/24/2018 06:00

API 05-123-05167	State/Province Colorado	County Weld	Field Name Non-Operated	Well Status	Total Depth (ftKB)	Primary Job Type Abandon Well
---------------------	----------------------------	----------------	----------------------------	-------------	--------------------	----------------------------------

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	1.00	07:00	CTRL	Crew Travel		
07:00	0.50	07:30	SRIG	Rig Up/Down	Fire Up equip, safety meeting	
07:30	4.25	11:45	RUTB	Run Tubing	RIH w/ 6 1/8" Tricone bit BHA Drilled thru cement from surface to 85', Continue Washing to 410', circulate hole clean.	
11:45	0.25	12:00	SRIG	Rig Up/Down	RD Power swivel, RU Tongs	
12:00	0.50	12:30	PULT	Pull Tubing	POOH	
12:30	1.00	13:30	GOP	General Operations	Wait for cement crew, cement crew cancelled.	
13:30	0.50	14:00	SRIG	Rig Up/Down	Winterize Equip. Secure WH, SDFN	
14:00	1.00	15:00	CTRL	Crew Travel		
15:00	15.00	06:00	inactive	inactive		

(Unknown) Porter 3 3/24/2018 06:00 - 3/25/2018 06:00

API 05-123-05167	State/Province Colorado	County Weld	Field Name Non-Operated	Well Status	Total Depth (ftKB)	Primary Job Type Abandon Well
---------------------	----------------------------	----------------	----------------------------	-------------	--------------------	----------------------------------

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	0.75	06:45	CTRL	Crew Travel		
06:45	0.50	07:15	SRIG	Rig Up/Down	Fire Equip, safety meeting, MU mule shoe BHA	
07:15	0.25	07:30	TRIP	Tripping	TIH to 400'	
07:30	1.00	08:30	SRIG	Rig Up/Down	Spot & RU Ranger Cement Equip, circulate hole, hold safety meeting	
08:30	1.00	09:30	CEMT	Surface Plug	Pump Surface plug: pump 5bbls fresh, establish circulation, pump 317sks, 1.15 yield, glass G cement, 15.8ppg, 65bbls slurry, saw cement returns to surface after 63bbls	
09:30	0.50	10:00	PULT	Pull Tubing	POOH TBG & mule shoe	
10:00	1.00	11:00	SRIG	Rig Up/Down	ND BOPs & spool, top wellbore off to surface with cement	
11:00	1.00	12:00	SRIG	Rig Up/Down	RDMO Ensign Rig #312 & Ranger Cement Equip	
12:00	1.00	13:00	CTRL	Crew Travel		
13:00	17.00	06:00	inactive	inactive		