

Donnelly Casing Pulling Co.

Phone 522-1410

P.O. Box 791
Sterling, Colorado 80751

RECEIVED
Bob Donnelly
AUG 15 1975

COLO. OIL & GAS CONS. COMM.
INVOICE DATE 8-5-75

SOLD TO Thomas G. Vessels
600 South Cherry Street
Suite 1220
Denver, Colorado 80222

WELL Bauman Ranch
Battlement #1

INVOICE NO. 442

Pulled rods and tubing		\$ 500.00
6824' 4 1/2" OD Casing @	35¢ per foot	2388.40
Day Work, 27 hours @	\$20.00 per foot	540.00
Pump, cement, 1 job	\$200.00 per job	200.00
Water truck, 16 hours @	\$15.00 per hour	240.00
Cement, 90 sacks @	\$3.25 ea. + tax	301.28
		<u>\$4169.68</u>

DATE	DAY WORK	REMARKS
7-11-75	0 hours	Moved unit. Dug deadmen. Pulled 115 rods and 57 tubing.
7-14-75	0 hours	Pulled rods and tubing.
7-15-75	12 hours	Dug cellar. Ran sand 7827' to 7590'. Loaded the hole. Set in floor. Dumped 5 sacks cement on top of sand. Worked pipe to 55". Water truck, 8 hours.
7-16-75	10 hours	Worked pipe to 65". Ran shot to 6700'. Pulled 4 joints.
7-17-75	0 hours	Jacked 21 joints.
7-18-75	0 hours	Jacked 20 joints.
7-19-75	0 hours	Pulled 85 joints.
7-21-75	5 hours	Pulled pipe to 800'. Pumped cement to 630', 60 sacks. Pulled pipe, 247 total. Tore out floor. Set 15 sacks cement in bottom of surface. Filled with mud to 30'. Set 10 sacks to 3' below ground level. Cut off head. Tallied pipe. Water truck, 3 hours. Pump job.

WELL COMPLETE

THANK YOU



00289934

file