



S (Durango) (SUBMIT IN TRIPLICATE)

Indian Agency **Southern Ute**

Compass (Denver)

1 Compass (Form) UNITED STATES

1 File DEPARTMENT OF THE INTERIOR

Allottee _____

GEOLOGICAL SURVEY

Lease No. **14-20-151-12**

SUNDRY NOTICES AND REPORTS ON WELLS

MAR 23 1962

NOTICE OF INTENTION TO DRILL	SUBSEQUENT REPORT OF WATER SHUT-OFF
NOTICE OF INTENTION TO CHANGE PLANS	SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING
NOTICE OF INTENTION TO TEST WATER SHUT-OFF	SUBSEQUENT REPORT OF ALTERING CASING
NOTICE OF INTENTION TO REDRILL OR REPAIR WELL	SUBSEQUENT REPORT OF REDRILLING OR REPAIR
NOTICE OF INTENTION TO SHOOT OR ACIDIZE	SUBSEQUENT REPORT OF ABANDONMENT
NOTICE OF INTENTION TO PULL OR ALTER CASING	SUPPLEMENTARY WELL HISTORY
NOTICE OF INTENTION TO ABANDON WELL	

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

U. S. GEOLOGICAL SURVEY
DURANGO CO. CO.

March 2, 1962

Well No. **1-10** is located **1590** ft. from **SW** line and **1510** ft. from **W** line of sec. **10**

NE 1/4 Sec 10 (1/4 Sec and 1/4 No.) **32N** (Twp.) **10W** (Range) **104N** (Meridian)

Ignacio Blanco (Field) **La Plata** (County or Subdivision) **Colorado** (State or Territory)

The elevation of the ~~ground~~ **ground** floor above sea level is **6595** ft.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

Spud 8:00 PM 1-27-62, Drilled 13 3/4" hole to 255' Ran 9 jts 9 5/8" O.D. 32.75#, H-40-J-55 T.E. 234' set at 246' RKB. Cemented w/185 sx 2% Cacl POB 8:00 AM 1-28-62. Good cement to surface.

Ran 115 jts 7" O.D. 20# J-55 SR STAC CF&I Csg T.E. 3637.30 set at 3625 RKB. Cemented w/100 sx HYS 400, 75 sx Inscr neat P.O.B. 6:15 PM 2-5-62. Good cement to surface.

Ran 78 jts 4 1/2" O.D. 9.5# J-55 SR STAC CF&I Csg T.E. 2490.81 set at 5954 RKB w/Burns liner hanger at 3463. Cemented w/160 sx 20% Diacel "D" - P.O.B. 6:00 AM Set neoprene seal - reversed out - no cement - Some gel water.

Ran 177 jts 1 1/4" O.D. 2.4# V-50 10R EVE Tbg. T.E. 5744.75 set at 5755 RKB.

I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company **Compass Exploration, Inc.**

Address **101 University Blvd.**

Denver 6, Colorado

By **Original signed by T. A. Dugan**

Title **Consulting Engineer**