

FORM

2

Rev
08/16

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

401617505

(SUBMITTED)

Date Received:

04/27/2018

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate
TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____Refilling ☒ZONE TYPE SINGLE ZONE ☐ MULTIPLE ZONES ☒ COMMINGLE ZONES ☒Sidetrack ☐

Well Name: VALLEY FARMS

Well Number: F21

Name of Operator: URS OPERATING COMPANY LLC

COGCC Operator Number: 10447

Address: 1600 BROADWAY ST STE 2600

City: DENVER

State: CO

Zip: 80202

Contact Name: CHRIS

MCRICKCARD

Phone: (720)508-8362

Fax: ()

Email: CMCRIKARD@URSARESOURCE.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20120125

WELL LOCATION INFORMATION

QtrQtr: NWSW Sec: 14 Twp: 6S Rng: 92W Meridian: 6

Latitude: 39.525629

Longitude: -107.642391

Footage at Surface: 2105 Feet FNL/FSL FSL 387 Feet FEL/FWL FWL

Field Name: MAMM CREEK

Field Number: 52500

Ground Elevation: 5613

County: GARFIELD

GPS Data:

Date of Measurement: 04/20/2006 PDOP Reading: 1.0 Instrument Operator's Name: HOLMES

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL FSL 1214 FWL 1882 FSL 1214 FWL
 Sec: 14 Twp: 6S Rng: 92W Sec: 14 Twp: 6S Rng: 92W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☒ is the mineral owner beneath the location.(check all that apply) ☒ is committed to an Oil and Gas Lease.☒ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

PLEASE SEE LEASE MAP ATTACHMENT PROVIDED WITH PREVIOUS APD SUBMITTALS.

Total Acres in Described Lease: 132 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 90 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 642 Feet
Building Unit: 791 Feet
High Occupancy Building Unit: 2459 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 449 Feet
Above Ground Utility: 1073 Feet
Railroad: 5280 Feet
Property Line: 246 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 305 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 707 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	191-50	160	SEC.14 - SW/4
WILLIAMS FORK	WMFK	191-24	160	SEC.14 - SW/4

DRILLING PROGRAM

Proposed Total Measured Depth: 8408 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: _____ Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☐ Annular Preventor ☐ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE

Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE

Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

If cuttings meet table 910 they will be beneficially reused.

Beneficial reuse or land application plan submitted? _____

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	65	0	80	70	80	0
SURF	12+1/4	8+5/8	32	0	1000	416	1000	0
1ST	7+7/8	4+1/2	11.6	0	8408	763	8408	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☒ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This Form 2 refile is being submitted to maintain the existing, open conductor pipe set for this well and future development plans. Conductor information provided on the Casing tab is actual, as-drilled information. The _ pad is an existing pad containing _ producing wells. There is no additional surface disturbance associated with this refile, therefore a refiled / amended Form 2A is not required at this time. No changes to the well location (SHL or BHL) or wellbore construction are proposed with this refile. There have been no changes in land use, mineral lease information or surface use agreement. Top of cement of 1st string/production casing will be >500 feet above top of gas.

Distance from completed portion to nearest completed portion of wellbore permitted/completed in the same formation measured to the Valley Farms F5 (045-14286). No non-op wells within 1500'.

Deviated drilling plan and directional data template provided with this refile. Please refer to previously approved APDs for all other required attachments.

This application is in a Comprehensive Drilling Plan No CDP #: _____

Location ID: 335538

Is this application being submitted with an Oil and Gas Location Assessment application? No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: JENNIFER LIND

Title: REGULATORY ANALYST Date: 4/27/2018 Email: JLIND@URSARESOURCES.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05 045 18287 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

--	--

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	An existing well on the pad logged with open-hole resistivity log with gamma-ray, from TD into the surface casing (Valley Farms F1, API 05-045-14290). All wells on the pad will have a cement bond log (CBL) with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs will state "No open-hole logs were run" and will clearly identify the type of log and the well (by API#) in which openhole logs were run.

Total: 1 comment(s)

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401617505	FORM 2 SUBMITTED
401632441	DEVIATED DRILLING PLAN
401632442	DIRECTIONAL DATA

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

Public Comments

No public comments were received on this application during the comment period.

