

FORM
5Rev
09/14State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

401419887

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10456

Contact Name: Reed Haddock

Name of Operator: CAERUS PICEANCE LLC

Phone: (720) 880-6369

Address: 1001 17TH STREET #1600

Fax: (303) 565-4606

City: DENVER State: CO Zip: 80202

API Number 05-045-23204-00

County: GARFIELD

Well Name: Puckett

Well Number: 33E-24

Location: QtrQtr: SESE Section: 24 Township: 6S Range: 97W Meridian: 6

Footage at surface: Distance: 647 feet Direction: FSL Distance: 718 feet Direction: FEL

As Drilled Latitude: 39.503032 As Drilled Longitude: -108.161942

GPS Data:

Date of Measurement: 03/21/2018 PDOP Reading: 2.4 GPS Instrument Operator's Name: Bart Hunting

** If directional footage at Top of Prod. Zone Dist.: 1365 feet. Direction: FSL Dist.: 1567 feet. Direction: FEL

Sec: 24 Twp: 6S Rng: 97W

** If directional footage at Bottom Hole Dist.: 1331 feet. Direction: FSL Dist.: 1682 feet. Direction: FEL

Sec: 24 Twp: 6S Rng: 97W

Field Name: GRAND VALLEY

Field Number: 31290

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 10/04/2017 Date TD: 10/09/2017 Date Casing Set or D&A: 10/12/2017

Rig Release Date: 03/13/2018 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 9158 TVD** 9055 Plug Back Total Depth MD 9073 TVD** 8970

Elevations GR 8150 KB 8180 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

CBL, PNL

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	20	52.8#	0	100	218	0	100	VISU
SURF	14+3/4	9+5/8	36#	0	2,492	865	0	2,492	VISU
1ST	8+3/4	4+1/2	11.6#	0	9,144	884	3,000	9,144	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
GREEN RIVER	0	2,991	NO	NO	
WASATCH	2,991	4,374	NO	NO	
WASATCH G	4,374	4,696	NO	NO	
FORT UNION	4,696	6,037	NO	NO	
OHIO CREEK	6,037	6,269	NO	NO	
WILLIAMS FORK	6,269	8,515	NO	NO	
CAMEO	8,515	8,979	NO	NO	
ROLLINS	8,979		NO	NO	

Comment:

All casing and cement information and formation tops are measured from KB. Per the approved Form 2 APD for the subject well, one gamma ray and one resistivity log was required for this multi-well pad. Please refer to the open hole logs submitted with the Puckett 33E-24-697 (API# 05-045-23204).

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Reed Haddock

Title: Sr. Regulatory Specialist

Date: _____

Email: rhaddock@caerusoilandgas.com

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
401423985	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
401424515	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
401424518	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401620612	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401620617	LAS-PULSED NEUTRON	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401620622	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401620631	PDF-PULSED NEUTRON	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401623739	WELL LOCATION PLAT	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401623747	LAS-TRIPLE COMBINATION	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401623748	PDF-COMPOSITE	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401623750	TIF-COMPOSITE	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)