

FORM
6Rev
05/18

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

401590669

Date Received:

03/29/2018

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 69175

Contact Name: Kelsi Welch

Name of Operator: PDC ENERGY INC

Phone: (303) 831-3974

Address: 1775 SHERMAN STREET - STE 3000

Fax:

City: DENVER State: CO Zip: 80203

Email: kelsi.welch@pdce.com

For "Intent" 24 hour notice required,

Name: _____ Tel: _____

COGCC contact:

Email: _____

API Number 05-123-17108-00

Well Name: JEFF

Well Number: 1

Location: QtrQtr: NENW Section: 14 Township: 6N Range: 66W Meridian: 6

County: WELD

Federal, Indian or State Lease Number: _____

Field Name: WATTENBERG

Field Number: 90750

☐ Notice of Intent to Abandon☒ Subsequent Report of Abandonment

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.494167

Longitude: -104.746944

GPS Data:

Date of Measurement: 01/18/2010

PDOP Reading: 1.6

GPS Instrument Operator's Name: Brandon Lucason

Reason for Abandonment:

☐ Dry☐ Production Sub-economic☐ Mechanical Problems☐ Other _____Casing to be pulled: ☐ Yes☐ No

Estimated Depth: _____

Fish in Hole: ☐ Yes☐ No

If yes, explain details below

Wellbore has Uncemented Casing leaks:

☐ Yes☐ No

If yes, explain details below

Details: _____

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
CODELL	7254	7264	03/20/2018	B PLUG CEMENT TOP	7020
NIOBRARA	7070	7096	03/20/2018	B PLUG CEMENT TOP	7020

Total: 2 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	12+1/4	8+5/8	24	359	255	359	0	
1ST	7+7/8	4+1/2	11.6	7,369	145	7,369	6,400	CBL

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 7020 with 2 sacks cmt on top. CIBP #2: Depth _____ with _____ sacks cmt on top.
CIBP #3: Depth _____ with _____ sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 250 sks cmt from 763 ft. to 0 ft. Plug Type: STUB PLUG Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐

Perforate and squeeze at 2500 ft. with 70 sacks. Leave at least 100 ft. in casing 2410 CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

(Cast Iron Cement Retainer Depth)

Set _____ sacks half in. half out surface casing from _____ ft. to _____ ft. Plug Tagged: ☐

Set _____ sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☐ No

Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: 655 ft. 4+1/2 inch casing Plugging Date: 03/21/2018
of _____

*Wireline Contractor: C&J

*Cementing Contractor: C&J

Type of Cement and Additives Used: 15.8#/gal CI G cement

Flowline/Pipeline has been abandoned per Rule 1105 ☐ Yes ☐ No

*ATTACH JOB SUMMARY

Technical Detail/Comments:

Procedure:

1. MIRU pulling unit. Pull 2 3/8" tubing.
2. RU wireline company.
3. TIH with CIBP. Set BP at 7020'. Top with 2 sxs 15.8#/gal CI G cement.
4. TIH with perf gun. Shoot holes in casing at 2500' and 2400'.
5. TIH with CICR. Set CICR at 2410'. Sting into CICR with tubing. Mix and pump 70 sxs 15.8#/gal CI G cement down tubing through squeeze holes. Sting out CICR leaving 10 sxs cement on top.
6. TIH with casing cutter. Cut 4 1/2" casing at 655'. Pull cut casing.
7. TIH with tubing to 763'. RU cementing company. Mix and pump 250 sxs 15.8#/gal CI G cement down tubing to surface.
8. Cut surface casing 6' below ground level and weld on cap.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kelsi Welch
Title: Production Tech Date: 3/29/2018 Email: kelsi.welch@pdce.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Jacobson, Eric Date: 5/15/2018

CONDITIONS OF APPROVAL, IF ANY: _____

<u>COA Type</u>	<u>Description</u>

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401590669	FORM 6 SUBSEQUENT SUBMITTED
401590675	CEMENT JOB SUMMARY
401590677	WELLBORE DIAGRAM
401590678	WIRELINE JOB SUMMARY

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)