

Daily Inspection Report  
Laramie Energy, LLC, Stormwater Management, 2018

**Buzzard Creek Project Area**

EI corrected a stormwater deficiency on the BCU 12B pad that was previously identified by COGCC. A water bar installed on the upper end of the fill slope had breached where a rock check held back too much runoff. EI repaired the breach and maintained the entire water bar. EI removed the rock check where the breach occurred and re-installed the material immediately in front of the flex hose outlet. EI also lowered all rock checks in the water bar to reduce the likelihood of reoccurrence.



**Breach in Water Bar on BCU 12B after Repairs**



**Water Bar on BCU 12B after Maintenance**