

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

401651470

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: CRYSTAL MCCLAIN

Name of Operator: KERR MCGEE OIL &amp; GAS ONSHORE LP

Phone: (720) 9294398

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

API Number 05-123-43272-00

County: WELD

Well Name: MARRS

Well Number: 3N-10HZ

Location: QtrQtr: SENW Section: 22 Township: 1N Range: 67W Meridian: 6

Footage at surface: Distance: 2075 feet Direction: FNL Distance: 2011 feet Direction: FWL

As Drilled Latitude: 40.038111 As Drilled Longitude: -104.879020

## GPS Data:

Date of Measurement: 05/23/2018 PDOP Reading: 2.5 GPS Instrument Operator's Name: JEREMY SHIVER

\*\* If directional footage at Top of Prod. Zone Dist.: 1502 feet. Direction: FNL Dist.: 1783 feet. Direction: FWL

Sec: 22 Twp: 1N Rng: 67W

\*\* If directional footage at Bottom Hole Dist.: 797 feet. Direction: FSL Dist.: 1803 feet. Direction: FWL

Sec: 10 Twp: 1N Rng: 67W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 02/24/2018 Date TD: 03/20/2018 Date Casing Set or D&amp;A: 03/21/2018

Rig Release Date: 03/24/2018 Per Rule 308A.b.

## Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 15728 TVD\*\* 7450 Plug Back Total Depth MD 15715 TVD\*\* 7450

Elevations GR 4981 KB 4998 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

## List Electric Logs Run:

GR, CBL, OHL RUN ON THE MARRS 28N-10HZ WELL (API: 05-123-43270).

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42	0	97	64	0	97	VISU
SURF	13+1/2	9+5/8	36	0	1,877	676	0	1,877	VISU
1ST	8+1/2	5+1/2	17	0	15,718	1,920	1,650	15,718	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
FOX HILLS	6,377				
SHARON SPRINGS	7,314				
NIOBRARA	7,347				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

Per Rule 317.p Exception, Open Hole Resistivity Logs have been run on the Marrs 28N-10HZ Well (API: 05-123-43270).

The Top of Productive Zone provided is an estimate based on the landing point at 8155' MD.

Completion is estimated for Q2 2018.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: CRYSTAL MCCLAIN

Title: REGULATORY ANALYST

Date: \_\_\_\_\_

Email: CRYSTAL.MCCLAIN@ANADARKO.COM

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
401651502	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
401651501	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
401651493	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401651495	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401651496	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401651497	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401651506	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)