

MARALEX RESOURCES
INC
P.O. Box 338
Ignacio, CO 81137



P.O. Box 1979, Farmington, NM 87499
(505) 325-2627

Name: South Shale Ridge 9-17
API:05-077-08610, Rig #01

Well Plugging Report

Cement Summary

P #1 - M & P 16 sks 18.88 cf 15.4 PPG Class B Cmt. from 3560' to 3344' TOC. WOC.

Work Detail

Start	Stop	PUX	Activity
06:30 AM	08:00 AM	P	Travel to location.
08:00 AM	09:30 AM	P	Service and start equipment. Road equipment, Spot equipment, RU equipment.
09:30 AM	03:30 PM	X	Wait on Rig crew. no tbg/csg test.
11:00 AM	05:00 PM	P	Travel to Grand Junction CO.
03:30 PM	05:30 PM	U	Attempt pump plug had issues w/ cmt. weight.
05:00 PM	05:01 PM	P	(Joey Alcon worked in Yard 2.5 HR) (Oscar Sanchez ST meeting/Yard work 2 HR)
05:30 PM	06:00 PM	P	P #1 M & P 16 sks 18.88 cf 15.4 PPG Class B Cmt. from 3560' to 3344' TOC. WOC.
06:00 PM	06:30 PM	P	Clean up secure equipment.
06:30 PM	07:30 PM	P	Travel to Grand Junction.

* P - Procedure Planned; U - Unplanned A+ issue; X - COA, Well Conditions

Crew:

Title	Name	Hours	Vehicle
Derrick:	Alcon, Joey	8.50	
Derrick:	Alcon, Joey	13.00	
Operator:	Sanchez, Oscar	8.00	
Operator:	Sanchez, Oscar	13.00	
Supervisor:	Comanche, Dereck	12.00	60 - Crew PU
Supervisor:	Comanche, Dereck	13.00	60 - Crew PU

On Site Reps:

Name	Association	Notes
M	BLM	CO. BLM on loc.
Jim Graves	Co. Rep.	W/ Maralex on loc.

Equipment:

#645 lgr. - WASTE PITS

MARALEX RESOURCES
INC

P.O. Box 338
Ignacio, CO 81137



P.O. Box 1979, Farmington, NM 87499
(505) 325-2627

Name: South Shale Ridge 9-17
API:05-077-08610, Rig #01

Well Plugging Report

Work Detail

Start	Stop	PUX	Activity
06:30 AM	08:00 AM	P	Travel to location
08:00 AM	08:30 AM	P	Service and start equipment
08:30 AM	11:30 AM	P	Wait on rig crew tag TOC at 3343', Trip pipe search for hole in csg w/ Packer, trip to get on depth for CR.
11:30 AM	01:30 PM	X	Wait on RMWS to arrive on location, Perf 4 HSC holes at 1473'. Pump and est. rate of 2.5 bbl a min. at 400 PSI.
01:30 PM	03:30 PM	P	Rig crew TIH set A Plus 4.5" CR at 1420' Pump and establish circulaion, sting in establish rate same.
03:30 PM	05:00 PM	P	P #2 Mix and Pump 30 sks 35.4 cf 15.3 PPG Class B Cmt. 1473' to 1388' TOC w/ 6 above, 4 below, and 20 out.
05:00 PM	06:30 PM	P	Crew LD all joints/ setting tool. RMWS RIH perf 4 HSC holes at 170'. Pump and attempt establish circulation pump 60 BBL almost out of water. No circulation, Will re-group in a.m. on plan. SDFD.
06:30 PM	07:30 PM	P	Travel to hotel.

* P - Procedure Planned; U - Unplanned A+ Issue; X - COA, Well Conditions

Crew:

Title	Name	Hours	Vehicle
Derrick:	Alcon, Joey	13.00	
Operator:	Sanchez, Oscar	13.00	
Supervisor:	Comanche, Dereck	13.00	60 - Crew PU

On Site Reps:

Name	Association	Notes
Ed Fancher	BLM	On loc.
Jim Graves	Co. Rep.	w/ Maralex on loc.

Equipment:

#645 lgr. - WASTE PITS

MARALEX RESOURCES
INC
P.O. Box 338
Ignacio, CO 81137



Name: South Shale Ridge 9-17
API:05-077-08610, Rig #01

Well Plugging Report

Work Detail

Start	Stop	PUX	Activity
06:30 AM	07:30 AM	P	Travel to location.
07:30 AM	08:00 AM	P	HSM on JSA. Service Start equipment.
08:00 AM	05:30 PM	X	RU A Plus Bentonite manifold. Pump 5 bbls fresh water, attempt jet Western clay Primegel sodium bentonite,keep plugging off shut down operations travel to Parachute CO. pick up 6-100 lbs bentonite, pre mix 8 bbls bentonite pump down BH disp. to 175' RD pumping equipment,travel to equipment to next location.
05:30 PM	06:30 PM	P	Travel to hotel.

* P - Procedure Planned; U - Unplanned A+ issue; X - COA, Well Conditions

Crew:

Title	Name	Hours	Vehicle
Derrick:	Alcon, Joey	12.00	
Operator:	Sanchez, Oscar	12.00	
Supervisor:	Comanche, Dereck	12.00	60 - Crew PU

On Site Reps:


Name	Association	Notes
Ed Fancher	BLM	On Loc.
Jim Graves	Co. Rep.	W/ Maralex on Loc.

Equipment:

#645 Igr. - WASTE PITS

MARALEX RESOURCES
INC

P.O. Box 338
Ignacio, CO 81137



P.O. Box 1979, Farmington, NM 87499
(505) 325-2627

Name: South Shale Ridge 9-17
API:05-077-08610, Rig #01

Well Plugging Report

Cement Summary

P #3 - Mix total 48 sks Pump total 40 w/ 3% cal. chlor. and LCM sks 47.2 cf 15.5 PPG Class B Cmt from 170' to 0' w/ no circ. out BH valve locked up w/ 500 PSI SIW. WOC.

Work Detail

Start	Stop	PUX	Activity
06:30 AM	08:00 AM	X	Travel to Location (South SHale Ridge 5-21)
08:00 AM	09:30 AM	X	RD pump and cmt equipment, road equipment to South Shale Ridge 9-17.
09:30 AM	12:30 PM	X	Spot in equipment, RU pump and cmt equipment. Pump 38 BBL fresh water down csg attempt est. circ. out BH valve no circ. W.O.O. Jennifer R. w/ BLM of spot 80 sks w/ 3% cal. chlor. and LCM cella flake and disp. 1 BBL past holes at 170'. Pre mix 3% cal. chlor. for 80 sks.
12:30 PM	01:30 PM	X	P #3 Mix total 48 sks Pump total 40 w/ 3% cal. chlor. and LCM sks 47.2 cf 15.5 PPG Class B Cmt from 170' to 0' w/ no circ. out BH valve locked up w/ 500 PSI SIW. WOC.
01:30 PM	02:00 PM	X	RD pump and cmt. equipment. MOL.

* P - Procedure Planned; U - Unplanned A+ issue; X - COA, Well Conditions

Crew:

Title	Name	Hours	Vehicle
Derrick:	Alcon, Joey	7.50	
Operator:	Sanchez, Oscar	7.50	
Supervisor:	Comanche, Dereck	7.50	60 - Crew PU

On Site Reps:

Name	Association	Notes
Jennifer Robinson	BLM	On loc.
Jim Graves	Co. Rep.	W/ Maralex on loc.

Equipment:

#645 lgr. - WASTE PITS



Date	Tuesday, September 26, 2017
Company	MARALEX
Lease/Well	SOUTH SHALE RIDGE s shale ridge 9-17
Supervisors	LANCE DECROW
Job Type	CIBP
Daily Ops	
Notable Complications	
Days on Job	1
Forecast	

Tower Time Log

[illegible]