

API #: 05-001-06811
Section 4
Township 2S , Range 66W
740' FS L& 660 FWL

SPUD 3/25/74
RKB: 5,163'
GL: 5,151'

CURRENT WELLBORE SCHEMATIC



12-1/4" OH

4'-104' 10 sxs

DENVER 198-128

8-5/8" 24# J-55 @ 214'

UPPER ARAPAHOE 446-229

CMT w/ 175 sxs

SQZ PERFS: 300'-302'

Circulated 90 sxs cmt

LOWER ARAPAHOE 757-521

SQZ PERFS: 600'-602'

Circulated 177 sxs cmt

STAGE 2 CMT 896'-1,460' (CBL - 7/13/16)

LARAMIE FOX HILLS 1365-1152

995'-1,500'

51 sxs Balanced Plug

Stage Tool @ 1,460' (CBL - 7/13/16),
CMT with 200 SXS

Displaced wellbore with 9.5# mud after
setting CIBP @ 8,200'

7 7/8" OH

STAGE 1 TOC - 7,380' (CBL - 7/13/16)

6,800'-6,900'

12 sxs Balanced Plug

CIBP @ 8,200' w/ 20' cmt on top

Muddy D-SAND PERFS: 8248' - 8258'

Retrievable BP @ 8,271'

UPPER J-SAND PERFS: 8303' - 8325'

LOWER J-SAND PERFS: 8341' - 8348'

Cmt Ret @ 8,333'

Perforations Squeezed with 50 sxs 5/11/1974

5-1/2" 14# K-55, @ 8,469'
CMT w/ 250 SXS

TD: 8,469' (MD)
PBTD: 8,271'

EVERETTE DAHLINGER #1
BUGLE FIELD

ADAMS COUNTY, COLORADO
BY: PAUL RYZA

DATE: 12/2/2016