

City and County of Denver

Date: 5/16/2018
Prepared by: JMB
Well Name: Champlin Amoco 117 A-1
Field: Third Creek
Legal: SWSE Sec. 7 T2S R65W

Geological tops
D Sand 8,216'
J Sand 8,264'

County: Denver
State: Colorado
GL: 5,295'
KB: 5,307'
API: 05-031-06388

Spud date: 11/13/1971
Completion date: 12/15/1971
Producing zone: J Sand

Hole Size: 12 1/4"
Surface Casing: 8 5/8" 24# K-55 ST&C
Cement Volume: 300 sx

Surface Casing Shoe 319'

Note: DV Estimated 1,650', CBL to be run to verify
Cement 2nd stage 300 sx

If TOC is not into surface casing will perf above TOC, set retainer and try to circ cement, leaving cement inside and outside of casing, volume dependent on depth

Set plug 100' below DV (per CBL) to 1,300'

TOC ?

CIBP 8,135' w/ 2 sx

Perforations
J Sand 8,290 - 8,308'
2 SPF

Hole Size 7 7/8 "
Production Casing 5 1/2" 14, 15.5 and 17#

Cement 1st stage 300 sx

Csg pt 8,398'
TD 8,398'

PBTD 8,364'

