

FORM
2

Rev
08/16

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401433911

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refiling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

01/19/2018

Well Name: Emmy State

Well Number: H36-753

Name of Operator: NOBLE ENERGY INC

COGCC Operator Number: 100322

Address: 1001 NOBLE ENERGY WAY

City: HOUSTON State: TX Zip: 77070

Contact Name: Brittany McFadden

Phone: (281)943-1940

Fax: ()

Email: brittany.mcfadden@nblenergy.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030009

WELL LOCATION INFORMATION

QtrQtr: SESW Sec: 25 Twp: 3N Rng: 65W Meridian: 6

Latitude: 40.190090

Longitude: -104.616670

Footage at Surface: 435 Feet FNL/FSL FSL 1275 Feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4816

County: WELD

GPS Data:

Date of Measurement: 04/03/2017 PDOP Reading: 1.6 Instrument Operator's Name: Scott Sherard

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FSL 330 FSL 2475 FWL 535 FSL 2427 FWL
Sec: 25 Twp: 3N Rng: 65W Sec: 36 Twp: 3N Rng: 65W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.
(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T3N-R65W, Sec. 23: NW/4, S/2, Sec. 25: NW/4, S/2, Sec. 27: NW/4, S/2, Sec. 33: NW/4, S/2, Sec. 35: NW/4, S/2; T2N-R65W, Sec. 1: N/2NW/4, S/2NW/4, S/2, Sec. 11: NW/4, S/2; T3N-R64W, Sec. 31: W/2W/2, E/2W/2, SE/4, Sec. 33: NW/4, S/2; T2N-R64W, Sec. 3: N/2NW/4, S/2NW/4, S/2, Sec. 5: N/2NW/4, S/2NW/4, S/2, Sec. 7: W/2W/2, E/2W/2, SE/4

Total Acres in Described Lease: 5709 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1866 Feet
Building Unit: 2197 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 3824 Feet
Above Ground Utility: 2719 Feet
Railroad: 5280 Feet
Property Line: 435 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 6 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 535 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

T3N-R65W, Sec. 25: SE/4SW/4, SW/4SE/4; 36: E/2W/2, W/2E/2

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		400	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 12700 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 342 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Drilling waste disposal information added to address non-oil based mud and fluids used in non-producing portion of wellbore.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: 2614238

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	42	0	80	144	80	0
SURF	13+1/2	9+5/8	36	0	1850	658	1850	0
1ST	8+1/2	5+1/2	20	0	12700	1369	12700	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments Noble respectfully submits this application for a permit to drill, which is a part of a twelve well pad producing to pad H25-15.

The distance to the nearest wellbore in the same formation is the DECHANT STATE H36-21D.

The Exception Location and Twinning Waiver language is included in the attached SUA, (Page 4, Section 8). Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112. Noble Energy shall isolate both the Fox Hills and Upper Pierre Aquifers with surface casing from hydrocarbon bearing zones and exposures to oil based drilling fluid. Noble Energy also agrees to not expose the Upper Pierre Aquifer to oil based mud.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Brittany McFadden

Title: Regulatory Analyst Date: 1/19/2018 Email: brittany.mcfadden@nblenergy.c

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: 6/1/2018

Expiration Date: 05/31/2020

API NUMBER

05 123 46976 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	<p>Prior to drilling operations, Operator will perform a risk analysis of the potential for subsurface collision with existing offset wells within close proximity of the proposed well, taking into consideration the possibility of well path drift for both the existing and proposed wells. Where inclination, MWD or gyro surveys of the offset wells are available, or can be reasonably obtained by the operator, such surveys shall be incorporated in the risk analysis, taking into account survey instrument margin of error. For the proposed well, upon conclusion of drilling operations, an as-constructed final directional survey will be submitted to the COGCC with the Form 5.</p>
	<p>Operator acknowledges the proximity of the non-operated listed wells. Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") stating that appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well. 05-123-11996, VON FELDT 1-25B 05-123-12550, CANNON FARMS 1-35C</p>
	<p>Operator acknowledges the proximity of the listed wells. Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") stating that appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well. 05-123-17434, KY BLUE H 25-10 05-123-14219, FOSTER UPRR 42-35 #2 05-123-15841, CANNON H 35-09 05-123-16043, SPIKE STATE GWS H 36-04 05-123-16311, SPIKE STATE H 36-12 05-123-16737, SPIKE STATE H 36-2J</p>
	<p>1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Comply with Rule 317.j. and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log. 3) Oil-based drilling fluid is to be used only after all fresh water aquifers are covered.</p>
	<p>Bradenhead tests shall be performed according to the following schedule and the Form 17 submitted within 10 days of each test: 1) Within 60 days of rig release and prior to stimulation and 2) If a delayed completion, 6 months after rig release and prior to stimulation. 3) Within 30 days after first production, as reported on Form 5A. If a bradenhead test reports a surface casing pressure greater than 200 psig stimulation is not allowed until the Engineering Supervisor has been consulted.</p>

Best Management Practices

No	BMP/COA Type	Description
1	General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with storm water runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
2	Drilling/Completion Operations	If a skid is performed for the subject well, then the only required BOPE tests are for the BOPE connection bonnet seal breaks, as long as a full BOPE test was performed at the beginning of the pad, and as long as all necessary BOPE tests are completed at least every 30 days during the pad operations.
3	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with open hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open hole logs were run.

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.
http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.
<http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf>

Attachment Check List

Att Doc Num	Name
401433911	FORM 2 SUBMITTED
401515475	OffsetWellEvaluations Data
401515476	DEVIATED DRILLING PLAN
401515480	OTHER
401515481	WELL LOCATION PLAT
401515482	DIRECTIONAL DATA
401538034	SURFACE AGRMT/SURETY
401538264	PROPOSED SPACING UNIT
401543776	EXCEPTION LOC REQUEST
401660244	OFFSET WELL EVALUATION

Total Attach: 10 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed	06/01/2018
Engineer	Corrected the number of sacks of cement for conductor string and corrected distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells with Operator's concurrence. Removed incorrect comment on submit tab about how the distance to a well belonging to another operator was determined. Missing BMP for anti-collision; added as COA. Removed BMP that should only be on Form 2A.	05/23/2018
Engineer	Emailed COAs for mitigation, waiting on response.	05/11/2018
Permit	Open Hole Logging BMP submitted by operator. Surface Use Agreement has waivers for Rule 318A.a & 318A.c. See page 4, Section 6. With operators concurrence changed distance to nearest well and updated comment. Permitting Review Complete.	04/22/2018
Permit	Passed Completeness.	02/16/2018
Permit	Returned to draft for: Missing Rule 318A.c Exception Location Request for twinning. Missing waiver in Amended SUA. (Page 4 is a map.)	02/01/2018
Permit	Returned to draft for: - the proposed measured depth on the "Drilling & Waste Plans" and "Casing" tabs does not match the proposed depth listed in the attached "DEVIATED DRILLING PLAN" and "DIRECTIONAL DATA"	01/29/2018

Total: 7 comment(s)