

FORM
5Rev
09/14State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

401639355

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10311

Contact Name: Christi Ng

Name of Operator: SRC ENERGY INC

Phone: (720) 616-4385

Address: 1675 BROADWAY SUITE 2600

Fax: (720) 616-4301

City: DENVER State: CO Zip: 80202

API Number 05-123-45393-00

County: WELD

Well Name: Boomerang

Well Number: 33N-6C-M

Location: QtrQtr: NENW Section: 5 Township: 5N Range: 66W Meridian: 6

Footage at surface: Distance: 1421 feet Direction: FNL Distance: 2327 feet Direction: FWL

As Drilled Latitude: 40.433250 As Drilled Longitude: -104.803567

GPS Data:

Date of Measurement: 01/03/2018 PDOP Reading: 3.1 GPS Instrument Operator's Name: Rob Wilson

** If directional footage at Top of Prod. Zone Dist.: 1225 feet. Direction: FNL Dist.: 2500 feet. Direction: FWL

Sec: 5 Twp: 5N Rng: 66W

** If directional footage at Bottom Hole Dist.: 1206 feet. Direction: FNL Dist.: 107 feet. Direction: FWL

Sec: 6 Twp: 5N Rng: 66W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 12/21/2017 Date TD: 01/24/2018 Date Casing Set or D&A: 01/25/2018

Rig Release Date: 04/06/2018 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 15626 TVD** 6963 Plug Back Total Depth MD 15499 TVD** 6964

Elevations GR 4773 KB 4793 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

MWD/LWD, CBL, MUD, (CNL in API 05-123-45997)

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	55	0	40	40	0	40	VISU
SURF	13+1/2	9+5/8	36	0	1,809	723	0	1,809	VISU
1ST	8+1/2	5+1/2	20	0	15,591	2,097	0	15,505	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,650		NO	NO	
SUSSEX	4,195		NO	NO	
SHANNON	4,794		NO	NO	
SHARON SPRINGS	6,937		NO	NO	
NIOBRARA	6,981		NO	NO	

Comment:

Top of productive zone footages are estimated and based on the top possible legal perforation point within the unit. The estimated date of completion of the pad is 3rd quarter 2018. The actual top of productive zone footages will be provided in the comments on the Form 5A when the well has been completed. The BHL footages are from the "Projection to Bit" numbers listed on the first page of the directional survey.

No open hole logs were run on this pad as a Rule 317.p exception was granted due to Dual Induction/Gamma Ray logs ran in the Wiedeman 6-5 (API 05-123-32052) and Wiedeman A-5-3-NBHZ (API 05-123-40064).

Surface and production casing setting depths on Surface Cement Job Summary and Production Cement Job Summary are incorrect. Reported depths on casing tab, 1809' is the accurate surface csg setting depth and 15591' is the accurate production csg setting depth. 6bbl wet shoe.

Each attachment and log run during the drilling and completion of a well is intended to fulfill a specific purpose. At times, vendors that run these logs or jobs put additional data in their report that is not critical or relevant to the technical purpose of their job. This data is not verified with SRC Energy and at times is not 100% accurate. For example, setting depths for a liner, date casing was set, or TD dates on a mud log may not be accurate. SRC Energy confirms setting depths through either daily drilling reports or liner reports, confirms date casing was set through daily drilling reports, and confirms TD through either our Pason system or daily drilling reports. Additionally, SRC Energy confirms liner tops through liner reports and not the CBL. Synergy is not able to request that these vendors not include this information in their report.

A formal as-drilled was performed and is attached with this submittal as verification of the surface location and ground elevation. Any other attachment that shows a different surface location or ground elevation is not accurate.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Christi Ng

Title: Sr. Regulatory Analyst

Date: _____

Email: cng@srcenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
401644722	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
401655218	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
401644644	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401644647	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401644679	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401644681	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401644715	LAS-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401644721	WELL LOCATION PLAT	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401644729	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401655273	PDF-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)