 SRC ENERGY	P&A Wellbore Diagram	
	Operator: SRC Energy	Operator #: 10311
	Well Name: JONES, WALTER 1-26	Location: Weld, CO
	API: 05-123-10999	Legal: SWNE 26-6N-66W

Actual

Deepest Water Well (1 mile): 80'

Well History

Spud Date: 02/08/1983

Perfs: Codell: 7102' - 7118'

Bradenhead History

Date of last test: 04/30/2018

Bradenhead pressure: 0 psi

Plugging Procedure

Tag existing CIBP w/ 2 sx (≈7004')

Set 36 sx on top of CIBP (462' plug)

Perforate @ 2500'

Set CICR @ 2400'





Pump 90 sx through CICR (300' annulus plug)

Set 10 sx on top of CICR (128' plug)

Cut casing @ 514'

Pump 269 sx @ 572' to surface

<u>Formations</u>	
Fox Hills (Btm)	854'
Sussex (Top)	4394'
Shannon (Top)	4816'
Niobrara (Top)	6795'
Codell (Top)	7102'

<u>Legend</u>	
	Existing Cement
	Cement Pumped
	CIBP
	CICR

