

 <b>SRC ENERGY</b>	<b>Re-Enter to Re-Plug Wellbore Diagram</b>	
	Operator: Apache Corporation	Operator #: 3380
	Well Name: Antelope 1-17	Location: Weld, CO
	API: 05-123-09510	Legal: SWNW 17-6N-66W

## Actual

**Deepest Water Well (1 mile): 600'**

### Well History

Spud Date: 10/01/1978

### Bradenhead History

Date of last test: N/A

Bradenhead Pressure: N/A

### Plugging Procedure

Set 155 sx @ 5462' (199' plug)

Tagged @ 5263'

Set 50 sx @ 5263' (63' plug)

Set 250 sx @ 4390' (344' plug)

Tagged @ 4046'

Set 150 sx @ 3994' (179' plug)

Tagged @ 3815'

Set 300 sx @ 2250' (352' plug)

Tagged @ 1898'

Pump 510 sx @ 810' to surface

Surface Plug: 0'-27'

Surface Hole: 13.75"

Surface Casing:

9.625" 36# @ 410'

250 sacks of cement

SC Shoe Plug: 340'-440'

810' - Surface Plug

Open Hole Plug:

1898'-2250'

Open Hole Plug:

3815'-3994'

Open Hole Plug:

4046'-4390'

Open Hole Plug:

5200'-5462'

### Formations

Sussex (Top) 4430'

Shannon (Top) 4775'

Niobrara (Top) 6943'

J-Sand (Top) 7697'

### Legend



Existing Cement



Cement Pumped



CIBP



CICR

Production Hole Size: 8.75"

TD: 9091'