



SRC ENERGY

**Operator:** Chandler & Associates LLC  
**Well Name:** Yancey 1  
**Legal:** NENE, Section 13, Township 6N, Range 67W  
**Location:** Weld County, CO  
**API:** 05-123-05227

Deepest Water Well  
Within 1 Mile = 620'

## Wellbore History

Spud Date: 3/16/1957

Surf Csg: 10.75", 40# @ 360' – 300 sx  
5.5", 15.5# @ 227' – 137 sx

Prod Hole: 8.75" @ 360'-7731'  
7.875" @ 7731'-9151'

\*Assumed Data

## Actual P&A Procedure

Lost circulation in surface casing, HIC  
TIH w/ 6 joints 5.5" 15.5# casing @ 227'  
Pump 137 sx, circulated to surface  
Ran CBL  
Tag previous plug @ 4325'  
Set 325 sx @ 4000' (460' plug)  
Tagged @ 3540'  
Set 50 sx @ 3530' (50' plug)  
Tagged @ 3480'  
Set 300 sx @ 2256' (356' plug)  
Tagged @ 1900'  
Set 532 sx @ 870' to surface

## Key



Existing Cement Coverage



CICR



Cement Pumped



CIBP

## Actual

