

Park 44-4
Current WBD

807' FSL475' FEL SESE 4 4N 63W 6th PM
Lat 40.33607 Long -104.43548
Weld County, Colorado
API #05-123-22697

Spud date 3/10/2005

4596 KB
4584 GL

8.625", 24#/ft Wt, Grade, 715', 12.25" hole
Cemented to surface w/ 290 sx.

TOC 5548'

Niobrara 6260'

Codell 6520'
Perfs 6521' - 6531'

J Sand 6988' '
Perfs 6990' - 7034'

4 1/2", 11.6#/ft, Grade, 7170, 7 7/8" hole
Cemented with 268 sxs

PBTD 7153 ft
TD 7171 ft 3/14/2005

Updated 6/4/2018 rcs

Park 44-4
Proposed WBD

807' FSL475' FEL SESE 4 4N 63W 6th PM
Lat 40.33607 Long -104.43548
Weld County, Colorado
API #05-123-22697

Spud date 3/10/2005

