

**Robert L. Bayless, Producer LLC**  
**PROPOSED Wellbore Schematic**  
**07/11/2017**

WELL HISTORY AS OF: 8-7-81  
 PHIDELPHIA CREEK NO. 32

BY: JRV

LOCATION: NE/4 SW/4 SEC 1 T2S R1D1W

RIO BLANCO COUNTY, CO.  
 MANCOS 'B' FORMATION

ELEV 6191

KB 6196

TD 3549

PBTD 3537

TCMT 2502 (CBL# T3)

PERFORATIONS: 20 HOLES

<u>3049</u>	<u>3134</u>	<u>3230</u>	<u>3280</u>
<u>3073</u>	<u>3150</u>	<u>3240</u>	<u>3286</u>
<u>3091</u>	<u>3177</u>	<u>3246</u>	<u>3309</u>
<u>3096</u>	<u>3190</u>	<u>3254</u>	<u>3314</u>
<u>3128</u>	<u>3223</u>	<u>3264</u>	<u>3319</u>
_____	_____	_____	_____
_____	_____	_____	_____

STIMULATION (9/8/80)

WATER: 45,402 gal 40# gel  
2% KCL H<sub>2</sub>O (5000 gal Pack)

SAND: 135,000# 20/40 sd  
28,000 # 100 mesh

ADDITIVES: 1100 SCF/BBL CO<sub>2</sub>  
1600# J-10

COST: \$ 48,492

**SCHEMATIC**

