

FORM
5Rev
09/14State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

401706173

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: CRYSTAL MCCLAIN

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

Phone: (720) 9294398

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

API Number 05-123-46269-00

County: WELD

Well Name: QUARTER CIRCLE

Well Number: 24-4HZ

Location: QtrQtr: SWSW Section: 24 Township: 1N Range: 67W Meridian: 6

Footage at surface: Distance: 344 feet Direction: FSL Distance: 1201 feet Direction: FWL

As Drilled Latitude: 40.030324 As Drilled Longitude: -104.844086

GPS Data:

Date of Measurement: 03/05/2018 PDOP Reading: 1.6 GPS Instrument Operator's Name: ROB WILSON

** If directional footage at Top of Prod. Zone Dist.: 1044 feet. Direction: FSL Dist.: 1045 feet. Direction: FWL

Sec: 24 Twp: 1N Rng: 67W

** If directional footage at Bottom Hole Dist.: 55 feet. Direction: FNL Dist.: 1060 feet. Direction: FWL

Sec: 13 Twp: 1N Rng: 67W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 03/08/2018 Date TD: 05/15/2018 Date Casing Set or D&A: 05/16/2018

Rig Release Date: 05/23/2018 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 17520 TVD** 7384 Plug Back Total Depth MD 17508 TVD** 7385

Elevations GR 4943 KB 4363 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

GR, CBL, OHL RUN ON THE QUARTER CIRCLE 24-2HZ WELL (API: 05-123-46266).

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42	0	100	64	0	100	VISU
SURF	12+1/4	9+5/8	36	0	1,861	467	0	1,861	VISU
1ST	8+1/2	5+1/2	17	0	17,511	2,130	290	17,511	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
FOX HILLS	657				
PARKMAN	4,163				
SUSSEX	4,964				
SHARON SPRINGS	7,259				
NIOBRARA	7,309				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

Per Rule 317.p Exception, Open Hole Resistivity Logs have been run on the Quarter Circle 24-2HZ Well (API: 05-123-46266).

The Top of Productive Zone provided is an estimate based on the landing point at 7482' MD.

As-drilled GPS data was taken after conductor was set.

Completion is estimated for Q3 2018.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: CRYSTAL MCCLAIN

Title: REGULATORY ANALYST

Date: _____

Email: CRYSTAL.MCCLAIN@ANADARKO.COM

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
401706276	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
401706275	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
401706263	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401706268	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401706273	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401706274	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401706279	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)