

## Weld County, Colorado, Northern Part

### 4—Ascalon fine sandy loam, 0 to 6 percent slopes

#### Map Unit Setting

*National map unit symbol:* 2tlp5

*Elevation:* 4,550 to 6,050 feet

*Mean annual precipitation:* 12 to 17 inches

*Mean annual air temperature:* 46 to 54 degrees F

*Frost-free period:* 135 to 160 days

*Farmland classification:* Farmland of statewide importance

#### Map Unit Composition

*Ascalon and similar soils:* 85 percent

*Minor components:* 15 percent

*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Ascalon

##### Setting

*Landform:* Interfluves

*Landform position (two-dimensional):* Backslope, summit

*Landform position (three-dimensional):* Interfluve

*Down-slope shape:* Linear

*Across-slope shape:* Linear

*Parent material:* Wind-reworked alluvium and/or calcareous sandy eolian deposits

##### Typical profile

*Ap - 0 to 7 inches:* fine sandy loam

*Bt1 - 7 to 13 inches:* sandy clay loam

*Bt2 - 13 to 18 inches:* sandy clay loam

*Bk - 18 to 48 inches:* sandy loam

*C - 48 to 80 inches:* sandy loam

##### Properties and qualities

*Slope:* 0 to 6 percent

*Depth to restrictive feature:* More than 80 inches

*Natural drainage class:* Well drained

*Runoff class:* Low

*Capacity of the most limiting layer to transmit water (Ksat):*

Moderately high to high (0.60 to 6.00 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Calcium carbonate, maximum in profile:* 10 percent

*Salinity, maximum in profile:* Nonsaline (0.1 to 1.9 mmhos/cm)

*Sodium adsorption ratio, maximum in profile:* 1.0

*Available water storage in profile:* Moderate (about 6.8 inches)

### **Interpretive groups**

*Land capability classification (irrigated): 3e*

*Land capability classification (nonirrigated): 4e*

*Hydrologic Soil Group: B*

*Ecological site: Sandy Plains (R067BY024CO)*

*Hydric soil rating: No*

### **Minor Components**

#### **Oldest**

*Percent of map unit: 8 percent*

*Landform: Interfluves*

*Landform position (two-dimensional): Backslope*

*Landform position (three-dimensional): Side slope*

*Down-slope shape: Linear*

*Across-slope shape: Linear*

*Ecological site: Sandy Plains (R067BY024CO)*

*Hydric soil rating: No*

#### **Otero**

*Percent of map unit: 7 percent*

*Landform: Interfluves*

*Landform position (two-dimensional): Footslope*

*Landform position (three-dimensional): Base slope*

*Down-slope shape: Linear*

*Across-slope shape: Linear*

*Ecological site: Sandy Plains (R067BY024CO)*

*Hydric soil rating: No*

## **Data Source Information**

Soil Survey Area: Weld County, Colorado, Northern Part

Survey Area Data: Version 12, Oct 10, 2017