

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

401699212

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: CRYSTAL MCCLAIN

Name of Operator: KERR MCGEE OIL &amp; GAS ONSHORE LP

Phone: (720) 9294398

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

API Number 05-123-46114-00

County: WELD

Well Name: AZUL

Well Number: 13-30HZ

Location: QtrQtr: SESW Section: 13 Township: 1N Range: 66W Meridian: 6

Footage at surface: Distance: 775 feet Direction: FSL Distance: 2446 feet Direction: FWL

As Drilled Latitude: 40.046166 As Drilled Longitude: -104.726214

## GPS Data:

Date of Measurement: 02/03/2018 PDOP Reading: 1.5 GPS Instrument Operator's Name: ROB WILSON

\*\* If directional footage at Top of Prod. Zone Dist.: 93 feet. Direction: FSL Dist.: 209 feet. Direction: FEL

Sec: 13 Twp: 1N Rng: 66W

\*\* If directional footage at Bottom Hole Dist.: 493 feet. Direction: FNL Dist.: 224 feet. Direction: FEL

Sec: 13 Twp: 1N Rng: 66W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 02/08/2018 Date TD: 04/07/2018 Date Casing Set or D&amp;A: 04/07/2018

Rig Release Date: 06/02/2018 Per Rule 308A.b.

## Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 13406 TVD\*\* 7461 Plug Back Total Depth MD 13394 TVD\*\* 7461

Elevations GR 5050 KB 5071 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

## List Electric Logs Run:

GR, CBL, CNL RUN ON THE AZUL 13-14HZ WELL (API: 05-123-46107).

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42	0	101	64	0	101	VISU
SURF	13+1/2	9+5/8	36	0	1,921	689	0	1,921	VISU
1ST	7+7/8	5+1/2	17	0	13,396	1,210	86	13,396	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
FOX HILLS	1,654				
PARKMAN	4,769				
SUSSEX	5,199				
SHARON SPRINGS	7,935				
NIOBRARA	7,965				
FORT HAYS	8,476				
CODELL	8,556				
CARLILE	8,665				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

Per Rule 317.p Exception, Compensated Neutron Logs have been run on the Azul 13-14HZ Well (API: 05-123-46107).

The Top of Productive Zone provided is an estimate based on the landing point at 8687' MD.

As-drilled GPS data was taken after conductor was set.

Completion is estimated for Q3 2018.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: CRYSTAL MCCLAIN

Title: REGULATORY ANALYST

Date: \_\_\_\_\_

Email: CRYSTAL.MCCLAIN@ANADARKO.COM

### Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
401699232	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
401699231	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
401699225	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401699228	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401699235	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401720080	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401720081	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)