

FORM
2

Rev
08/16

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401667386

Date Received:

07/13/2018

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Melbon Ranch

Well Number: 4H-17H-M265

Name of Operator: CRESTONE PEAK RESOURCES OPERATING LLC

COGCC Operator Number: 10633

Address: 1801 CALIFORNIA STREET #2500

City: DENVER

State: CO

Zip: 80202

Contact Name: Erin Lind

Phone: (720)410-8478

Fax: ()

Email: erin.lind@crestonepr.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20160104

WELL LOCATION INFORMATION

QtrQtr: SWSW Sec: 17 Twp: 2N Rng: 65W Meridian: 6

Latitude: 40.134715

Longitude: -104.696637

Footage at Surface: 1225 Feet FNL/FSL FSL 219 Feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4956

County: WELD

GPS Data:

Date of Measurement: 03/01/2018 PDOP Reading: 1.7 Instrument Operator's Name: Charlie Scott

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
890 FSL 460 FWL 890 FSL 460 FEL
Sec: 17 Twp: 2N Rng: 65W Sec: 17 Twp: 2N Rng: 65W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

N/2NE/4, S/2, Sec 17, T2N, R65W

Total Acres in Described Lease: 400 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease #

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 460 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1632 Feet
Building Unit: 1863 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 1206 Feet
Above Ground Utility: 1869 Feet
Railroad: 5280 Feet
Property Line: 219 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government:

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners:

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 116 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): Unit Number:

SPACING & FORMATIONS COMMENTS

Proposed Spacing Unit = Township 2 North, Range 65 West
S½ of Section 17

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		320	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 11927 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 246 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	42.09	0	98	78	98	0
SURF	13+1/2	9+5/8	40	0	2359	969	2359	0
1ST	8+1/2	5+1/2	20	0	11927	1650	11927	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments	Nearest well in same formation per anti-collision is then Crestone Peak operated Melbon Ranch 3A-17H, 123-34663. Nearest active outside operated well per anti-collision is the Kerr-McGee Oil & Gas operated HUDCO 39-18 (API: 05-123-33455). Exception location waiver granted in Section 15 of attached SUA.
----------	---

This application is in a Comprehensive Drilling Plan _____ No _____ CDP #: _____

Location ID: 428103

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes _____


I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Erin Lind

Title: Regulatory Analyst Date: 7/13/2018 Email: erin.lind@crestonepr.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: 

Director of COGCC Date: 8/31/2018

Expiration Date: 08/30/2020

API NUMBER

05 123 47754 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	<p>1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad.</p> <p>2) Comply with Rule 317.j. and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.</p> <p>3) Oil-based drilling fluid is to be used only after all fresh water aquifers are covered.</p>
	<p>Bradenhead tests shall be performed according to the following schedule and the Form 17 submitted within 10 days of each test:</p> <p>1) Within 60 days of rig release and prior to stimulation and</p> <p>2) If a delayed completion, 6 months after rig release and prior to stimulation.</p> <p>3) Within 30 days after first production, as reported on Form 5A.</p>
	<p>Operator acknowledges the proximity of the listed wells. Operator assures that this offset list will be remediated per the DJ Basin Horizontal Offset Policy (option 4). Operator will submit a Form 42 ("OTHER – AS SPECIFIED BY PERMIT CONDITION") stating that appropriate mitigation will be completed, during the hydraulic stimulation of this permitted well. This Form 42 shall be filed 48 hours prior to stimulation. Operator will assure that the offset well's Bradenhead is open and monitored during the entire stimulation treatment – a person will monitor for any evidence of fluid, a Bradenhead test will be performed prior to the beginning of stimulation. In addition, internal formation isolation is to be provided via either bridge plug or 100' cement plug within 100' of the top of the Niobrara.</p> <p>SANDLIN-WELD-COUNTY UNIT 2 (API 05-123-10924)</p>
	<p>Operator acknowledges the proximity of the listed non-operated wells. Operator assures that this offset list will be remediated per the DJ Basin Horizontal Offset Policy (option 3). Operator will submit a Form 42 ("OFFSET MITIGATION COMPLETED") stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p> <p>MELBON RANCH 1 (API 05-123-07258)</p> <p>MELBON RANCH 17-14 (API 05-123-18951)</p>

Best Management Practices

No	BMP/COA Type	Description
1	Drilling/Completion Operations	Prior to drilling operations, Crestone will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, the Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as constructed gyro survey will be submitted to COGCC with the Form 5.
2	Drilling/Completion Operations	Crestone will comply with the "COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area", dated May 29, 2012.
3	Drilling/Completion Operations	Rule 317.p Logging Program One of the first wells drilled on the pad will be logged with Cased hole Pulsed Neutron Log with Gamma Ray Log from the kick-off point to into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run in that well and have those logs attached. The Form 5 for each well shall clearly state "No open-hole logs were run" and shall reference the Rule 317.p Exception granted for the well.

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.
http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.
<http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf>

Attachment Check List

Att Doc Num	Name
401667386	FORM 2 SUBMITTED
401679058	OffsetWellEvaluations Data
401679092	DIRECTIONAL DATA
401679093	DEVIATED DRILLING PLAN
401679094	WELL LOCATION PLAT
401679095	SURFACE AGRMT/SURETY
401692324	PROPOSED SPACING UNIT
401692325	EXCEPTION LOC REQUEST
401692326	OPEN HOLE LOGGING EXCEPTION
401751576	OFFSET WELL EVALUATION

Total Attach: 10 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed.	08/30/2018
Engineer	Corrected distance to nearest active non-op well and text in operator comment.	08/29/2018
Engineer	SB5 773-517' L-FH Wells 875' 44-1 mi	08/29/2018
Engineer	317.r No active non-op wellbores within 150'. 317.s No stimulation setback consents required.	08/29/2018
Permit	Passed Completeness.	07/19/2018

Total: 5 comment(s)