

FORM  
5Rev  
09/14State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

401499179

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10456

Contact Name: Reed Haddock

Name of Operator: CAERUS PICEANCE LLC

Phone: (720) 544-3267

Address: 1001 17TH STREET #1600

Fax: (303) 565-4606

City: DENVER State: CO Zip: 80202

API Number 05-045-23398-00

County: GARFIELD

Well Name: Puckett

Well Number: 12C-26-697

Location: QtrQtr: SENW Section: 26 Township: 6S Range: 97W Meridian: 6

Footage at surface: Distance: 2257 feet Direction: FNL Distance: 1656 feet Direction: FWL

As Drilled Latitude: 39.495046 As Drilled Longitude: -108.190869

GPS Data:

Date of Measurement: 08/21/2018 PDOP Reading: 1.4 GPS Instrument Operator's Name: TLL

\*\* If directional footage at Top of Prod. Zone Dist.: 1808 feet. Direction: FNL Dist.: 464 feet. Direction: FWL

Sec: 26 Twp: 6S Rng: 97W

\*\* If directional footage at Bottom Hole Dist.: 1812 feet. Direction: FNL Dist.: 311 feet. Direction: FWL

Sec: 26 Twp: 6S Rng: 97W

Field Name: GRAND VALLEY

Field Number: 31290

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 12/21/2017 Date TD: 12/26/2017 Date Casing Set or D&amp;A: 12/27/2017

Rig Release Date: 07/09/2018 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 8892 TVD\*\* 8753 Plug Back Total Depth MD 8779 TVD\*\* 8640

Elevations GR 8322 KB 8352 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

CBL, PNL

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	20	54#	0	100	218	0	100	VISU
SURF	14+3/4	9+5/8	40#	0	2,500	866	0	2,500	VISU
1ST	8+3/4	4+1/2	11.6#	0	8,828	949	4,583	8,828	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
GREEN RIVER	0	4,346	NO	NO	
WASATCH G	4,346	4,639	NO	NO	
FORT UNION	4,639	5,861	NO	NO	
OHIO CREEK	5,861	6,034	NO	NO	
WILLIAMS FORK	6,034	8,239	NO	NO	
CAMEO	8,239	8,683	NO	NO	
ROLLINS	8,683		NO	NO	

Comment:

All casing and cement information and formation tops are measured from KB. Per the approved Form 2 APD for the subject well, one gamma ray and one resistivity log was required for this multi-well pad. Please refer to the open hole logs submitted with the Puckett 13D-26-697 (API# 05-045-23418).

The well logs uploaded contain both the CBL and the PNL data.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Reed Haddock

Title: Sr. Regulatory Specialist

Date: \_\_\_\_\_

Email: rhaddock@caerusoilandgas.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
401499193	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
401499287	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
401499288	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401734722	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401734726	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401755477	WELL LOCATION PLAT	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)