

WELLBORE DIAGRAM
NGL Water Solutions DJ LLC
ROY SWD 2
SHL: NWNE Sec 28-T1N-R66W
Weld County , CO
API unassigned

Planned

8/29/2018

HRG

K.B.= 5063

G.L.= 5047

16

TOPS

All listed in MD

Niobrara - 8,000'

Codell - 8,492'

10-3/4", 40.5# J-55 ST&C CSG Set @ 1175' (14-3/4" O.H.)
Cmt'd w/ 402 sx total

DV Tool @ 8776' (MD), 7776' (TVD)
Cmt'd w/ 906 sx lead, 252 sx tail (TOTAL 1158 sx 2nd stage)

EOT & Packer @ 10,046' (5-1/2" tbg)

PBR & TOL @ 10,096'

Lyons - 10,148'

Lower Satanka - 10,278'

Wolfcamp - 10,528'

Amazon - 10,580'

Council Grove - 10,630'

7-5/8" 29.7# HCL-80 CSG Set @ 10,148 (MD) 9,107' (TVD) (9-7/8" O.H.)
Cmt'd w/ 254 sx (1st stage)

Slotted Pipe

Admire - 10,846'

Virgil - 10,880'

Missouri - 11,073'

Fountain - 11,253'

Slotted Pipe Liner slotted with 2" by 0.040" slots on 6" centers

TD - 12,164'

MD = 12,164'

5-1/2" 17# N-80 LT&C Slotted LNR (TOL @ 10,148', EOL @ 12,164')
(6-5/8" O.H.)

NOT TO SCALE