

WELL NAME:	Scott 21C-36-692				FIELD:	MAMM CREEK		
QTR QTR:	NWNE	SEC:	36	TWN:	6S	RNG:	92W	
COUNTY:	Garfield			ST:	CO	API:	05-045-21471-00	
KB:	17'	GL:	5894'	TD:	7280'			
Revised: 9/11/18		Purposed Wellbore Diagram						

CASING DETAILS

PURPOSE	HOLE SIZE	CASING SIZE	WEIGHT	GRADE	SET DEPTH	CMT	CMT TOP
CONDUCTOR	26"	16"	42#	H-40	40'	GROUT	0'
SURFACE	12 1/4"	9 5/8"	36#	J-55	710'	230 sks	0'
PRODUCTION	8 3/4"	4 1/2"	11.6#	HCP-110	7280'	780 sks	2189

FORMATION TOPS	
LOWER WASATCH	2689
OHIO CREEK	3027
MESAVERDE	3356
WMFK	3356
TOP_OF GAS	4832
CAMEO	6812
ROLLINS	7015

PBTD: 7260'
TD: 7280'