

WELL NAME:	Kaufman 42C-24-692			FIELD:	MAMM CREEK		
QTR QTR:	NWSE	SEC:	24	TWN:	6S	RNG:	92W
COUNTY:	Garfield			ST:	CO	API:	05-045-23559
KB:	17'	GL:	5864'	TD:	7843'		
Revised: 9/11/18		Purposed Wellbore Diagram					

CASING DETAILS

PURPOSE	HOLE SIZE	CASING SIZE	WEIGHT	GRADE	SET DEPTH	CMT	CMT TOP
CONDUCTOR	26"	16"	65#	H-40	80'	194 sks	0'
SURFACE	12 1/4"	9 5/8"	36#	J-55	800'	340 sks	0'
PRODUCTION	7 7/8"	4 1/2"	11.6#	HCP-110	7843'	943 sks	2745'

FORMATION TOPS	
LOWER WASATCH	3245
OHIO CREEK	3579
MESAVERDE	3968
WMFK	3968
TOP_OF_GAS	5294
CAMEO	7459
ROLLINS	7596

PBTD: 7823'
TD: 7843'