



OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Perforate Dakota Sand	<input checked="" type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
		Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME McCallum Unit WELL NO. 8
FIELD McCallum Unit WILDCAT COUNTY Jackson
LOCATION SE SE Section 12 Township 9N Range 79W Meridian 6th PM
(Quarter Quarter)
660 feet from S Section Line and 660 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

Moved in pulling unit and killed well with water. Pulled tubing. Ran correlation log and perforated 7" production casing opposite the Dakota sand from 5520' - 5525' RBM and from 5540' - 5560' RBM with 2 jet shots per foot. Re-Ran tubing, swabbed well in and released pulling unit.

Before perforating well tested 7 bbls. oil, 2,296 MCF of CO₂ gas and 10 bbls. of water per day on 4-13-61.

After perforating well tested 8 bbls. oil, 1,739 MCF of CO₂ gas and 22 bbls. of water per day on 5-25-61.

AJJ	
DVR	
WRS	
HHM	
JAM	✓
FJP	✓
JJD	✓
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Company Continental Oil Company Date 6-9-61

JUN 16 1961

Address Box 126, Craig, Colorado Phone No. TA 4-6571

Date

By [Signature] Title Dist. Supt.

Director

(Signature)