

## OIL AND GAS CONSERVATION COMMISSION

DEPARTMENT OF NATURAL RESOURCES

THE STATE OF COLORADO

duplicate for Patented and Federal lands.  
File in triplicate for State lands.

RECEIVED

AUG 11 1970

COLO. OIL &amp; GAS CONS. COMM.

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1.

OIL WELL ☒ GAS WELL ☐ OTHER ☐

2. NAME OF OPERATOR

GASCO, Inc.

3. ADDRESS OF OPERATOR

1600 Sherman Street, Denver, Colo. 80203

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.  
See also space 17 below.)

At surface

2230' EWL &amp; 2440 NSL of Section 3

At proposed prod. zone

NE NE SW

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

8007 G.L.

5. LEASE DESIGNATION AND SERIAL NO.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Blevins

9. WELL NO.

B-6

10. FIELD AND POOL, OR WILDCAT

Canadian River

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

Sec. 3-T.9N., R.78W.

12. COUNTY

Jackson

13. STATE

Colo.

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

## NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON ☒CHANGE PLANS ☐

## SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

8-28-70

Date of work

T.D. 2130' 5-1/2" Csg. @ 2130' 8-5/8" Csg. @ 313'  
Perforations 2058-60, 2033-46, 2010-18.

This well is now non-commercial. It is proposed to plug and abandon this well as follows:

Dump bailer 8 sx of cement over the perforations up to 1980'  
Cut the 5-1/2" casing at the lowest free-point and pull.  
Set 20 sx. plug 50' in & 50' above the 5-1/2" stub.  
Set 30 sx. plug over bottom of surface csg. from 265' to 365'  
Cut top of 8-5/8" off 3 ft. below ground level. \*\*  
Set top plug of 5 sx. in 8-5/8" and weld on plate over top.  
Intervals between plugs in the hole will be filled with heavy mud.

\*\* This well in hay meadow where it will be possible to till over.

18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE Agent/GASCO, Inc.

DATE 8-10-70

(This space for Federal or State office use)

DIRECTOR

APPROVED BY

TITLE

O &amp; G CONS. COMM.

DATE

AUG 13 1970

CONDITIONS OF APPROVAL, IF ANY: