

OIL AND GAS CONSERVATION COMMISSION
DEPARTMENT OF NATURAL RESOURCES
OF THE STATE OF COLORADO

File in duplicate for Patented and Federal lands;
 File in triplicate for State lands.



00285524

SEP -2 1970

. & GAS CONS. COMM.

LEASE DESIGNATION AND SERIAL NO.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
 Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
2. NAME OF OPERATOR GASCO, Inc.		7. UNIT AGREEMENT NAME	
3. ADDRESS OF OPERATOR 1600 Sherman Street, Denver, Colo. 80203		8. FARM OR LEASE NAME Blevins	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 2230' EWL & 2440' NSL of Section 3 At proposed prod. zone NE NE SW		9. WELL NO. B-6	
14. PERMIT NO.		10. FIELD AND POOL, OR WILDCAT Canadian River	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 8007 G.L.		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 3-T.9N., R.78W.	
		12. COUNTY Jackson	
		13. STATE Colo.	

16. **Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data****NOTICE OF INTENTION TO:**TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON ☐CHANGE PLANS ☐**SUBSEQUENT REPORT OF:**WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT ☒

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. **DESCRIBE PROPOSED OR COMPLETED OPERATIONS** (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work Aug. 26, 1970

Plugged & Abandoned as follows:

Pulled 1" and 2-3/8" tubing strings from packers at 2035' and 1988' depths.
 Pumped 8 sx. cement plug with top plug down casing with 45 bbls. Plug from 1877' to 1950'.
 Cut 5-1/2" casing at 895' depth. Pulled casing.
 Ran 2-3/8" tubing to top of stub. Could not get into stub.
 Set 20 sx cement plug thru tubing from 810' to 898' depth.
 Set 30 sx cement plug thru tubing from 275' to 375' depth.
 Set 10 sx. cement plug from 30' to top of 8-5/8" casing.
 Welded plate in top of 8-5/8" casing 3 ft. below ground level.
 Interval between plugs heavy mud.

Plugged & Abandoned Aug. 26, 1970

DVR	<input checked="" type="checkbox"/>
FJP	<input checked="" type="checkbox"/>
HHM	<input checked="" type="checkbox"/>
JAM	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>

18. I hereby certify that the foregoing is true and correct

SIGNED

R. S. Higgins

TITLE

Agent/GASCO, Inc.

DATE

8-31-70

(This space for Federal or State office use)

DIRECTOR

O & G CONS. COMM.

APPROVED BY

W. Rogers

TITLE

DATE

SEP 2 1970

CONDITIONS OF APPROVAL, IF ANY:

✓
Report

Ex Oil Prod.