



COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS

333-3

(Indicate nature of data by checking below)

- Notice of intention to drill _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report X _____

Following is a ~~(notice of intention to do work)~~ (report of work done) October 16 19 52
(patented) described as follows:

<u>Colorado</u>	<u>Logan</u>	<u>Dale</u>
<u>State</u>	<u>County</u>	<u>Field</u>
<u>A-2</u>	<u>Haywood</u>	<u>NE 23</u>
<u>(Well No.)</u>	<u>(Lease)</u>	<u>(Sec. and 1/4 Sec.)</u>
		<u>8N</u>
		<u>53W</u>
		<u>(Twp.)</u>
		<u>(Range)</u>
		<u>(Meridian)</u>

The well is located 330 ft. (N) of N Line and 996 ft. (E) of E Line of NE/4 Sec. 23-8N-53W (S) (W)

The elevation above sea level is 4059 ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

- 10-3-52 Spudded
- 10-6-52 Ran and cemented 8 5/8" casing at 605' with 300 sacks.
- 10-10-52 Core #1 4637-82' Recovered 45' shale and siltstone.
- 10-13-52 DST #1 4635-4645' open 1 hour. Good blow in 15 minutes. Decreased to weak in 30 minutes. Recovered 690' water with thin scum of oil. Sand none to trace visible porosity, no oil stain. Very scattered SF, faint to fair ECF. DST #2 4750-80' open 32 minutes. Recovered 1530' water with no show of oil.
- 10-14-52 Spotted cement plug from 4790 feet to 4600 feet. Then placed mud taken from the bottom of the mud pit from 4600' to 620' where a cement plug was spotted to 530 feet. Then heavy mud was run to 10 feet where a cement plug was placed to the surface in such a manner as not to interfere with surface cultivation.

Schlumberger Tops:

'Muddy' 4634' Dakota 4734'

Approved: OCT 20 1952

Company Shell Oil Company

J. E. Gray
Director

Address Denham Bldg., Denver, Colorado

By W. M. Inabnet
FOR J. E. GRAY

Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triuplicate for school and state lands.