




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS

333-3



OIL & GAS
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well x _____
 Report of work done on well since previous report _____

Following is a (notice of intention to do work) October 13, 1952
 (~~report of work done~~) (~~Goodland~~)
 (patented) described as follows:

<u>Colorado</u>	<u>Logan</u>	<u>Dale</u>	<u>Field</u>
State	County		
<u>A-2</u>	<u>Haywood</u>	<u>NE/4 23</u>	<u>8N 53W</u>
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)	(Twp.) (Range) (Meridian)

The well is located 330 ft. (NW) of N Line and 996 ft. (E) of East Line of NW/4 Section 23-8N-53W.
 (S) (W)

The elevation above sea level is 4059 ft.*

Details of Plan of Work: (State names of and expected depths to objective sands:
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
 ing points, and all other important proposed work.)

We propose to plug and abandon the captioned well by spotting a cement plug from
 4790 feet to 4600 feet opposite the 'Muddy' and Dakota sandstone. Heavy mud taken
 from the bottom of the mud pit will then be placed from 4600 feet to 620 feet, 15
 feet below the bottom of the surface casing. A cement plug will be placed from 620
 feet to 530 feet. Heavy mud will be placed to within 10 feet of the surface where
 a cement plug will be spotted to the surface in such a manner as not to interfere with
 surface cultivation.

Approved: OCT 15 1952

J. J. Zorichak
Director

Company Shell Oil Company

Address Denham Bldg., Denver, Colorado

By W. M. Enabnit
FOR J. E. GRAY

Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented
lands and in Triplicate for school and state lands.

*Verbal approval to plug and abandon this well was given to Mr. A. H. Weider, Shell Ex-
ploitation Engineer, by Mr. J. J. Zorichak, Director of the Conservation Commission on Oct.