

API NO. 05-121-10402

00047970

NOTICE OF INTENT TO ABANDON

COMPANY VIS-OP OILBY SCOTT GIBSONPHONE # 768-1835WELL NAME WALTER RINNE #1

LOCATION

QQ SE SE SECTION 35 TWP 2N RNG 53WCOUNTY WASHINGTON

ESTIMATED DATE OF WORK _____

WELL DATA _____ DA X EXISTING WELLOBJECTIVE/PR FORMATION "D" SAND TOTAL DEPTH 4939'PLUG BACK TD 4891' PERFS 4783' - 4788'
4790' - 4793'

TESTS OR SHOWS _____

FORMATION TOPS	
FORMATION	DEPTH
"D" SAND	4748'
"J" SAND	4848'

SURFACE CASING 166 FEET OF 8 5/8 INCH CASINGPRODUCTION CASING 4924 FEET OF 5 1/2 INCH CASING

OFFSET WELLS YES X NO _____

COMPLETED IN _____ DISTANCES FROM WELL _____

STAGE TOOL REQUIRED FOR AQUIFER COVERAGE YES _____ NO _____

AQUIFERS NOT COVERED BY SURFACE CASING X NONE

AQUIFER	DEPTH

PLUGGING PROCEDURE

PULL CASING YES X NO _____ TOC 3945'

1. _____ SKS FROM _____ FT UP OR CIBP @ 4730' W/2SKS CMT

2. _____ SKS FROM _____ FT UP _____

3. _____ SKS FROM _____ FT UP _____

4. _____ SKS FROM _____ FT UP _____

5. 40 SKS 1/2 IN 1/2 OUT SURFACE CASING * SEE BELOW

6. 10 SKS @ SURFACE

7. CUT 4 FEET BELOW GROUND LEVEL, WELD ON PLATE

8. _____ SKS IN RAT HOLE

9. _____ SKS IN MOUSE HOLE

10. RESTORE LOCATION

* IF CASING CANNOT BE PULLED, PERFORATE SQUEEZE HOLES
AT 210'. SPOT 40 SX CEMENT PLUG INSIDE & OUTSIDE CASING
THROUGH SQUEEZE HOLES.

APPROVED BY D. K. Wilson

DATE 9-27-95