

# OIL AND GAS CONSERVATION COMMISSION DEPARTMENT OF NATURAL RESOURCES OF THE STATE OF COLORADO

File in duplicate for Patented and Federal lands.  
File in triplicate for State lands.

RECEIVED

JAN 12 1971

COLO. OIL & GAS CONS. COMM.

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER XX		5. LEASE DESIGNATION AND SERIAL NO.	
2. NAME OF OPERATOR Plains Exploration Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR 1135 Petroleum Club Bldg., Denver, Colo.		7. UNIT AGREEMENT NAME	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface SWNW - 660' EWL and 1980' SNL  At proposed prod. zone  "D" and "J" Sands		8. FARM OR LEASE NAME Newsom	
14. PERMIT NO. 70-697		9. WELL NO. 1	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 4473 KB		10. FIELD AND POOL, OR WILDCAT Wildcat	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 35-2N-55W	
		12. COUNTY Morgan	13. STATE Colorado

### 16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

#### NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETION

ABANDON

CHANGE PLANS

#### SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other) Dec. 29, 1970

REPAIRING WELL

ALTERING CASING

ABANDONMENT XX

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work December 29, 1970

DVR	
FJP	
HHM	
JAM	
JJD	

The well was plugged December 29, 1970, by filling it with heavy mud from the total depth to the bottom of the surface pipe (5048-90). A 15-sack cement plug was set in the bottom 45 feet of the surface pipe (90-45), then the casing was filled with heavy mud to within 30 feet of the top. A 10-sack cement plug was set in the top 30 feet of the surface pipe (40-10).

All measurements are taken from the Kelly bushing, which was approximately 8 feet above the ground.

18. I hereby certify that the foregoing is true and correct

SIGNED

Richard W. Volk

TITLE Exploration Manager

DATE January 8, 1971

(This space for Federal or State office use)

APPROVED BY

TITLE

DIRECTOR  
O & G CONS. COMM.

DATE

JAN 13 1971

CONDITIONS OF APPROVAL, IF ANY: