



Extraction Oil & Gas Completion Report

Date: 12/11/2016 Well Name: Frank Cavanaugh 1 Wellbore Info: Total Depth MD: 0 ft KOP: 0 ft Total Depth TVD: 0 ft Liner Top: N/A ft Surface Casing: 10.75" Intermediate: 0 Prod. Liner: 0 Frac String: None	AFE #: 221602 County: Weld State: Colorado KB: 10 ft Tubing: N/A
---	---

Cost Summary

Item	Description	Amount	Cost	SEC	Daily Total	Cum. Total
	Concord Well service	\$5,000.00	\$0.00		\$6,600.00	
	Slaugh fishing	\$550.00	\$0.00		\$9,150.00	
		\$0.00	\$0.00			
		\$0.00	\$0.00			
Completion Supervisor:	Day: Randy Williams		Cost:	SEC	\$1,050.00	
	Night:		Cost:		\$0.00	

Crucial notes: (Information placed here will be forwarded to all following sheets)

Summary of Operations

Date: 12/11/16 **Rig:** Concord

07:00- Safety meeting, spot in pipe wrangler, set pipe racks, and load tbg on pipe racks, and tally
 10:00- Make up 6.75" cone bit, bit sub, 2- 3.5" drill collars tag cement @ 60', (ran a total of 8 DC) RU PS and drill cement fell thru @ 210'
 13:00- Continue IH and tag @ 300' circ and swivel IH to 326' returning heavy sand, circ clean.
 15:00- Swivel IH w/ 3 jts never tagged RD PS and TIH to 430' tag fill, RU PS and swivel IH and clean out to 450'
 16:00- Circ clean and TOOH
 17:00- Secure well and SDFN