



Service Order #: 74080

Date: 02-Oct-18

Well Name	Location	County	St	API#
MONTAGUE JH #5			CO	
Formation	Cement Via	Type Of Service	Well Type	Age
	TUBING	PLUG		REWORK
				AFE#
				PO#

Customer:

SCHNEIDER PUMPING

P.O. BOX 297

FORT MORGAN

CO 80701

Remarks:

CLASS G CEMENT, 1.15 YIELD, 15.8 LBS/GAL
40 SKS, 8.1 BBLS
1791' - 1654'
40 SKS, 8.1 BBLS
1000' - 865'
50 SKS, 10.2 BBLS
185' - 0' (SURFACE)

Customer Rep:

PH:

WELLBORE DATA				
Type	Size	Weight	Depth	Volume
Surface Casing:	8.625	22.7	132.0	
Production Casing:				
Intermediate:				
Drill Pipe:				
Tubing:	2.875	6.5	1,791.0	
Type	Size	Depth (Top)	Depth (Bot)	Volume
Liner:				
Open Hole:	7.875			

OTHER DATA

BHT	Max PSI	Total Depth

Packer or Retainer Type / Depth:

--	--

Perf Depths:	#	Total
	0	0
	0	
	0	

TIME	PUMP RATES		DENSITY	PRESS	STG TOT	TOTAL	REMARKS
	WATER (gpm)	PUMP (bpm)	(lb/gal)	(psi)	(bbls)	(bbls)	
13:09	0	0.0	6.88	2,530	0.1	0.1	PSI TEST
13:10	0	0.5	6.88	0	0.0	0.0	H2O SPACER
13:14	55	0.6	15.60	6	5.0	5.0	CEMENT
13:19	0	2.5	15.89	6	8.1	13.6	DISPLACEMENT
13:23	0	0.6	7.86	0	9.1	22.8	OFF LINE
13:47	0	0.0	6.88	0	0.0	0.0	H2O SPACER
13:53	0	1.5	15.79	11	3.6	3.6	CEMENT
13:58	0	2.0	15.87	0	8.1	11.7	DISPLACEMENT
14:00	0	1.9	8.48	0	4.9	17.1	OFF LINE
14:39	0	0.5	6.98	0	0.0	0.0	H2O SPACER
14:44	0	1.8	15.94	0	3.6	3.6	CEMENT
14:49	1	2.0	14.52	0	10.2	13.8	OFF LINE

Summary

Max Fl. Rate	Avg Fl. Rate	Max Psi	Avg Psi
2.5	0.6	2,530	9

Customer Acknowledgement:

Service Rating:

- ☐ Satisfactory
☐ Unsatisfactory

Cementer:

RAFAEL GARCIA

PRODUCTS USED

--

SCHNEIDER ENERGY
MONTAGUE JH #5



