

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

401693704

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10456

Contact Name: Reed Haddock

Name of Operator: CAERUS PICEANCE LLC

Phone: (720) 880-6369

Address: 1001 17TH STREET #1600

Fax: (303) 565-4606

City: DENVER State: CO Zip: 80202

API Number 05-045-23771-00

County: GARFIELD

Well Name: NPR

Well Number: 12D-10-596

Location: QtrQtr: NESW Section: 10 Township: 5S Range: 96W Meridian: 6

Footage at surface: Distance: 1912 feet Direction: FSL Distance: 2454 feet Direction: FWL

As Drilled Latitude: 39.627575 As Drilled Longitude: -108.156069

## GPS Data:

Date of Measurement: 10/12/2018 PDOP Reading: 4.3 GPS Instrument Operator's Name: Dayton Slaugh

\*\* If directional footage at Top of Prod. Zone Dist.: 1972 feet. Direction: FNL Dist.: 1479 feet. Direction: FWL

Sec: 10 Twp: 5S Rng: 96W

\*\* If directional footage at Bottom Hole Dist.: 1989 feet. Direction: FNL Dist.: 1312 feet. Direction: FWL

Sec: 10 Twp: 5S Rng: 96W

Field Name: GRAND VALLEY

Field Number: 31290

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 07/08/2018 Date TD: 07/18/2018 Date Casing Set or D&amp;A: 07/19/2018

Rig Release Date: 08/30/2018 Per Rule 308A.b.

## Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 9715 TVD\*\* 9430 Plug Back Total Depth MD 9653 TVD\*\* 9368

Elevations GR 6709 KB 6733 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

## List Electric Logs Run:

CBL, PNL

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	20	54#	0	100	218	0	100	VISU
SURF	14+3/4	9+5/8	36#	0	2,383	528	0	2,383	VISU
1ST	8+3/4	4+1/2	11.6#	0	9,698	921	7,995	9,698	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
GREEN RIVER	0	3,905	NO	NO	
WASATCH G	3,905	4,369	NO	NO	
FORT UNION	4,369	6,157	NO	NO	
OHIO CREEK	6,157	6,493	NO	NO	
WILLIAMS FORK	6,493	8,915	NO	NO	
CAMEO	8,915	9,599	NO	NO	
ROLLINS	9,599		NO	NO	

Comment:

All casing and cement information and formation tops are measured from KB. Per the approved Form 2 APD for the subject well, one gamma ray and one resistivity log was required for this multi-well pad. Please refer to the open hole logs submitted with NPR 14A-10-596 (API 05-045-23777).

The well logs uploaded contain both the CBL and the PNL data.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Reed Haddock

Title: Sr. Regulatory Specialist

Date: \_\_\_\_\_

Email: rhaddock@caerusoilandgas.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
401704262	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
401707437	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
401707438	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401782009	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401782018	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401802907	WELL LOCATION PLAT	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)