

GREAT WESTERN 26-53 Date: 2/19/2017

AFE No: MTG-2017 **Daily Completion and Workover Report** **DOL: 2**

REPT NO. 2	OPERATOR GREAT WESTERN OPERATING COMPANY LLC	FIELD NAME WATTENBERG	SUPERVISOR / ENGINEER MARK TIBBS / MICHEAL ANDREWS	ST NO. 00
SPUD DATE 08/28/2006	API 05-123-24054	STATE COLORADO	COUNTY WELD	DIVISION GREAT WESTERN OPERA

OPERATIONS AT RPT TIME
 POOH WITH TUBING, CHANGE OUT WELLHEAD TO 5K SYSTEM.

24 HR SUMMARY
 MIRU HWS # 45, BLEED DOWN WELL, PUMP 20 BBLS DOWN CASING AND TUBING, POOH, RIH AND SET 4.5" CIBP @ 6717', POOH LAY DOWN SETTING TOOL.

24 HR FORECAST
 REMOVE AND REPLACE WELLHEAD TO 5K SYSTEM, RIH WITH 2.375" TUBING, LAND. COMPLETE MITIGATION. RDMO

GL ELEV 4,749.0 (usft)	RKB 4,761.0 (usft)	FORMATION	TMD 7,276	TVD 7,276	PBTMD 7,251	PBTVD 7,251
AUTH COST /				DAY COST / CUM COST \$9,150 / \$9,150		

CASING DETAILS									
ASSEMBLY	SIZE	INST DATE	FROM (usft)	TO (usft)	SIZE	WEIGHT	GRADE	THRDS	

TUBING DETAILS									
ASSEMBLY	SIZE	INST DATE	FROM (usft)	TO (usft)	SIZE	WEIGHT	GRADE	THRDS	
		01/20/2017	0.0	6,686.5	2.375				

PERFORATIONS							
FORMATION/ZONE	DATE	SIDETRK #	STATUS	TYPE	TOP (usft)	BASE (usft)	

HOURS	DUR (hr)	PHASE	CODE	SUB	DESCRIPTION
00:00 - 07:00	7.00	MITIGATE	MTG PLANNED - MITIGATION		WSI, CREW TRAVEL
07:00 - 09:00	2.00	MITIGATE	MTG PLANNED - MITIGATION		MIRU HWS #45
09:00 - 10:00	1.00	MITIGATE	MTG PLANNED - MITIGATION		BLEED DOWN WELL AND PUMP 20 BBLS DOWN TUBING AND CASING, NIPPLE UP BOP, RIG UP FLOOR
10:00 - 12:00	2.00	MITIGATE	MTG PLANNED - MITIGATION		POOH, 1-10' PUP, 1-8' PUP AND 217 JTS. 7091'
12:00 - 14:00	2.00	MITIGATE	MTG PLANNED - MITIGATION		MAKE UP 4.5" CIBP, RIH TO 6700', 206 JTS
14:00 - 15:00	1.00	MITIGATE	MTG PLANNED - MITIGATION		SET 4.5 CIBP @ 6717', LAY DOWN 1 JTS FILL HOLE WITH FRESH AND CIRCULATE HOLE, TEST CASING TO 500 PSI FOR 15 MIN, (GOOD TEST)
15:00 - 17:00	2.00	MITIGATE	MTG PLANNED - MITIGATION		POOH
17:00 - 00:00	7.00	MITIGATE	MTG PLANNED - MITIGATION		WSI