

# Tompkins 41AWI-08-07-95

SEC 08 T7S R95W

API NO. 05-045-22551

Garfield County, Colorado

## Current WBD

10/11/2018

Not to scale

ELEVATION

KB 5549'

Spud date: 11/10/17

### Surface Casing:

9 5/8" 36# K-55 Set @ 1726'

Cemented to surface

264 sacks

### Production Casing:

5 1/2" 17.0# P-110 Set @ 8105'

TOC: 2452'

Williams Fork 4018'

Cameo 6664'

Rollins 7111'

Cozzette 7398'

Corcoran 7660'

### Perforations

7413' - 7959'

Packer set at 7359'

2-7/8" Injection Tubing  
Set at 7363'

