

Donnelly Casing Pulling Co.

Phone 522-1410

P.O. Box 791
Sterling, Colorado 80751

Bob Donnelly

SOLD
TO

Energy Minerals Corp.
3100 Denver Place
999 18th St.
Denver, Co. 80202-2431

INVOICE DATE 4-16-90



00225703

WELL N

Dickerson #1

INVOICE NO. 90-252

5567' 4½" OD Casing @	\$.60 per foot	\$3340.20
Day Work, 41 hours @	\$ 50.00 per hour	2050.00
Cement, 40 sacks @	\$ 7.50 each	300.00
	tax	9.00
Shots, 2 @	\$ 30.00 per shot	60.00
Pump Job, 1 @	\$550.00 per job	550.00
Water Truck, 11 hours @	\$ 38.00 per hour	418.00
Welder, 4 hours @	\$ 21.00 per hour	84.00
1800' 1" Tubing @	\$.20 per foot	360.00
Forklift, 1 hour (unloading) @	\$ 35.00 per hour	35.00
Hauled pipe to our yard:		
Mack Trucks, 10 hours @	\$ 42.00 per hour	420.00
Trailers, 10 hours @	\$ 10.00 per hour	100.00
Helper, 5 hours @	\$ 14.00 per hour	70.00
Mud, 5 sacks @	\$ 5.60 per sack	28.00
		<u>\$7824.20</u>

DATE	DAY WORK	REMARKS
3-14-90	0 hours	Moved rig.
3-15-90	9 hours	Raised mast. Ran sand from 6490' to 6350'. Dug cellar. Rigged up jacks. Worked pipe to 12". Set 5 sacks cement on sand at 6350'. Water truck, 3 hours.
3-19-90	10 hours	Ran 53 joints spotting tubing. Mixed 5 sacks mud. Pumped 2 loads mud and 20 bbls. oil. Pump job. Water truck, 8 hours. 5 sacks mud.
3-20-90	8 hours	Pulled spotting tubing. Pressured up on well. Worked pipe from 12" to 15".
3-21-90	6 hours	Worked pipe from 15" to 60". Ran a shot to 5600'. Worked pipe from 60" to 75".
3-22-90	4 hours	Worked pipe. Ran a shot to 5500'. Worked pipe loose. Pulled 82 joints casing.
3-23-90	0 hours	Pulled casing.
3-27-90	4 hours	Tore out floor. Set 25 sacks cement in and out bottom of surface. Filled with mud to 30'. Set 10 sacks cement to 4' below ground level. Welded on cap.

WELL COMPLETE

THANK YOU

All open accounts are due by 10th of month following purchase. All amounts 30 days past due will be charged a FINANCE CHARGE at 1½% per month or an ANNUAL PERCENTAGE RATE of 18%.