

SILVER APPELYARD FED PAD
MULTI-WELL PLAN

NOTES:

1. THIS FIELD SURVEY CONFORMS TO THE MINIMUM STANDARDS SET BY THE COGCC, RULE NO. 215
2. ALL DISTANCES AND BEARINGS SHOWN HEREON ARE GROUND VALUES AS GPS MEASURED IN THE FIELD, WITH TIES TO WELLS MEASURED PERPENDICULAR TO LINES SHOWN HEREON. THIS LOW DISTORTION PROJECTION (LDP) IS BASED ON THE NORTH AMERICAN DATUM OF 1983, U.S. SURVEY FOOT WITH A LATITUDE ORIGIN OF 40.654245°N, A CENTRAL MERIDIAN LONGITUDE OF 104.315474°W, AND A SCALE FACTOR ON THE CENTRAL MERIDIAN OF 1.000233 (EXACT). THE LDP BASIS OF BEARINGS IS GEODETIC NORTH.
3. FIELD VERIFICATION OF MONUMENTS COMPLETED WITHIN 1 YEAR OF SIGNATURE DATE, UNLESS OTHERWISE NOTED.

NOTES:

- SILVER APPELYARD FED 27-34-1HC TO BE AT 535' FSL & 2549' FWL.
BOTTOM HOLE AT 600' FSL & 790' FWL, SEC. 34.
- SILVER APPELYARD FED 27-34-2HN TO BE AT 535' FSL & 2569' FWL.
BOTTOM HOLE AT 600' FSL & 975' FWL, SEC. 34.
- SILVER APPELYARD FED 27-34-3HN TO BE AT 535' FSL & 2589' FWL.
BOTTOM HOLE AT 600' FSL & 1345' FWL, SEC. 34.
- SILVER APPELYARD FED 27-34-4HN TO BE AT 535' FSL & 2609' FWL.
BOTTOM HOLE AT 600' FSL & 1715' FWL, SEC. 34.
- SILVER APPELYARD FED 27-34-5HC TO BE AT 535' FSL & 2629' FWL.
BOTTOM HOLE AT 600' FSL & 1900' FWL, SEC. 34.
- SILVER APPELYARD FED 27-34-6HN TO BE AT 535' FSL & 2649' FWL.
BOTTOM HOLE AT 600' FSL & 2085' FWL, SEC. 34.
- SILVER APPELYARD FED 27-34-7HN TO BE AT 535' FSL & 2669' FWL.
BOTTOM HOLE AT 600' FSL & 2455' FWL, SEC. 34.
- SILVER APPELYARD FED 27-34-8HN TO BE AT 535' FSL & 2689' FWL.
BOTTOM HOLE AT 600' FSL & 2455' FEL, SEC. 34.
- SILVER APPELYARD FED 27-34-9HN TO BE AT 535' FSL & 2709' FWL.
BOTTOM HOLE AT 600' FSL & 2085' FEL, SEC. 34.
- SILVER APPELYARD FED 27-34-10HC TO BE AT 535' FSL & 2729' FWL.
BOTTOM HOLE AT 600' FSL & 1900' FEL, SEC. 34.
- SILVER APPELYARD FED 27-34-11HN TO BE AT 535' FSL & 2591' FEL.
BOTTOM HOLE AT 600' FSL & 1715' FEL, SEC. 34.
- SILVER APPELYARD FED 27-34-12HN TO BE AT 535' FSL & 2571' FEL.
BOTTOM HOLE AT 600' FSL & 1345' FEL, SEC. 34.
- SILVER APPELYARD FED 27-13HN TO BE AT 535' FSL & 2551' FEL.
BOTTOM HOLE AT 0' FSL & 975' FEL, SEC. 27.
- SILVER APPELYARD FED 27-14HC TO BE AT 535' FSL & 2531' FEL.
BOTTOM HOLE AT 0' FSL & 790' FEL, SEC. 27.
- SILVER APPELYARD FED 27-15HN TO BE AT 535' FSL & 2511' FEL.
BOTTOM HOLE AT 0' FSL & 605' FEL, SEC. 27.

LEGEND

- = EXISTING MONUMENT ○ = CALCULATED POSITION
▲ = LANDING POINT LP = LANDING POINT
⬤ = BOTTOM HOLE BHL = BOTTOM HOLE
● = PROPOSED WELL

