

FORM  
2  
Rev  
08/16

State of Colorado  
Oil and Gas Conservation Commission  
1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:  
401657830

APPLICATION FOR PERMIT TO:

Drill       Deepen       Re-enter       Recomplete and Operate

Date Received:  
07/27/2018

TYPE OF WELL    OIL     GAS     COALBED     OTHER \_\_\_\_\_  
ZONE TYPE      SINGLE ZONE     MULTIPLE ZONES     COMMINGLE ZONES

Refilling   
Sidetrack

Well Name: BEIERLE      Well Number: 26-16HZ  
Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP      COGCC Operator Number: 47120  
Address: P O BOX 173779  
City: DENVER      State: CO      Zip: 80217-3779  
Contact Name: LISA SCHINDLER      Phone: (720)929-3091      Fax: (720)929-7267  
Email: LISA.SCHINDLER@ANADARKO.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

WELL LOCATION INFORMATION

QtrQtr: NWNE      Sec: 26      Twp: 1N      Rng: 66W      Meridian: 6  
Latitude: 40.028279      Longitude: -104.740974  
Footage at Surface: 460 Feet      FNL/FSL      FNL 1684 Feet      FEL/FWL      FEL  
Field Name: WATTENBERG      Field Number: 90750  
Ground Elevation: 5120      County: WELD  
GPS Data:  
Date of Measurement: 05/07/2018      PDOP Reading: 1.3      Instrument Operator's Name: PRESTON KNUTSEN  
If well is     Directional       Horizontal (highly deviated)      **submit deviated drilling plan.**  
Footage at Top of Prod Zone:    FNL/FSL      FEL/FWL      Bottom Hole:    FNL/FSL      FEL/FWL  
   47      FSL      266      FEL      27      FNL      335      FEL  
   Sec: 23      Twp: 1N      Rng: 66W      Sec: 23      Twp: 1N      Rng: 66W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership:     Fee       State       Federal       Indian  
The Surface Owner is:     is the mineral owner beneath the location.  
(check all that apply)     is committed to an Oil and Gas Lease.  
    has signed the Oil and Gas Lease.  
    is the applicant.  
The Mineral Owner beneath this Oil and Gas Location is:     Fee       State       Federal       Indian  
The Minerals beneath this Oil and Gas Location will be developed by this Well:    Yes  
The right to construct the Oil and Gas Location is granted by:    oil and gas lease  
Surface damage assurance if no agreement is in place:      Surface Surety ID: \_\_\_\_\_

**LEASE INFORMATION**

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 1 North, Range 66 West, 6th P.M.  
Section 26: NE/4  
Weld County, Colorado

Total Acres in Described Lease: 160 Described Mineral Lease is:  Fee  State  Federal  Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

**CULTURAL DISTANCE INFORMATION**

Distance to nearest:

Building: 873 Feet  
Building Unit: 1013 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 457 Feet  
Above Ground Utility: 854 Feet  
Railroad: 5280 Feet  
Property Line: 460 Feet

**INSTRUCTIONS:**

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).  
- Enter 5280 for distance greater than 1 mile.  
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.  
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

**DESIGNATED SETBACK LOCATION INFORMATION**

Check all that apply. This location is within a:  Buffer Zone  
 Exception Zone  
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit  
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 05/07/2018

**SPACING and UNIT INFORMATION**

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 119 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 992 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

**SPACING & FORMATIONS COMMENTS**

T1N-R66W; SEC 13: SWSW; SEC 14: SESE; SEC 23: E2E2; SEC 24: W2W2; SEC 25: NWNW; SEC 26: NENE

**OBJECTIVE FORMATIONS**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		480	GWA

## DRILLING PROGRAM

Proposed Total Measured Depth: 13503 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 304 Feet  No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type:  Annular Preventor  Double Ram  Rotating Head  None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

SEE COMMENTS SECTION

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	36.94	0	80	64	80	0
SURF	13+1/2	9+5/8	36	0	1500	590	1500	0
1ST	7+7/8	5+1/2	17	0	13493	1584	13493	

Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

**OTHER LOCATION EXCEPTIONS**

Check all that apply:

Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_

Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

**OPERATOR COMMENTS AND SUBMITTAL**

Comments

Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent possible, at which point they will either be land applied or taken to a licensed, commercial disposal site; the decision will be based upon laboratory analysis of fluids. KMG will reuse oil-based drilling fluids to the maximum extent possible, at which point they will be returned to the fluids manufacturer for reconditioning or disposal at a licensed, commercial disposal site.

Cuttings disposal: If the surface owner authorizes, and if it is feasible for this location at the time of drilling, water-based cuttings will be disposed of onsite using bioremediation/solidification product. If the surface owner does not authorize onsite disposal and/or it is not feasible for this location at the time of drilling, water-based cuttings will be disposed of using a Centralized E&P Waste Management facility or a private spread field. Oil-based cuttings will be disposed of offsite and at a licensed, commercial disposal site.

The following well(s) belong to Kerr-McGee and will have treated intervals within one hundred fifty (150) feet of this proposed well:  
BEIERLE 26-8HZ

The following well(s) belong to Kerr-McGee and the proposed well will be within one hundred fifty (150) feet of the existing well(s) vertical section:  
NONE

The following well(s) are not within 150' of KMG's proposed well, however may appear to be less than 150' in 2D view:  
NONE

Nearest well in the same formation is the BEIERLE 26-8HZ well at 119', as confirmed by anticollision analysis

This application is in a Comprehensive Drilling Plan       No       CDP #: \_\_\_\_\_

Location ID:       440489      

Is this application being submitted with an Oil and Gas Location Assessment application?       Yes      

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name:       LISA SCHINDLER      

Title:       SR REGULATORY ANALYST       Date:       7/27/2018       Email:       DJREGULATORY@ANADARK      

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:       *[Signature]*       Director of COGCC Date:       11/9/2018      

Expiration Date:       11/08/2020      

**API NUMBER**  
05 123 48581 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>
	This Permit to Drill is approved subject to all the BMPs and COAs on the most recently approved Form 2A and any subsequently approved Form 4 for the Oil and Gas Location. The most recently approved Form 2A and any subsequent Form 4s containing applicable COAs for this location shall be posted onsite during construction, drilling, and completions operations.
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Comply with Rule 317.j. and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Oil-based drilling fluid is to be used only after all fresh water aquifers are covered.
	Bradenhead tests shall be performed according to the following schedule and the Form 17 submitted within 10 days of each test: 1) Within 60 days of rig release and prior to stimulation and 2) If a delayed completion, 6 months after rig release and prior to stimulation. 3) Within 30 days after first production, as reported on Form 5A. If a bradenhead test reports a surface casing pressure greater than 200 psig stimulation is not allowed until the Engineering Supervisor has been consulted.

## Best Management Practices

<b>No</b>	<b>BMP/COA Type</b>	<b>Description</b>
1	Drilling/Completion Operations	Kerr-McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
2	Drilling/Completion Operations	Anti-Collision: Kerr-McGee will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within one hundred fifty (150) feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators within one hundred fifty (150) feet prior to drilling.
3	Drilling/Completion Operations	317.p Logging Program: One of the first wells drilled on the pad will be logged with Open Hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.
4	Drilling/Completion Operations	604c.(2).H. BOPE: Our rigs at a minimum will have a double ram with blind and pipe ram and annular preventer.
5	Drilling/Completion Operations	604c.(2).I. BOPE Testing for Drilling Operations: BOPEs will be tested upon rig-up and, at a minimum, every 30 days.
6	Drilling/Completion Operations	604c.(2).J. BOPE for Well Servicing Operations: Blowout prevention equipment will be used on any servicing operations associated with this well. Backup stabbing valves will be used during any future servicing operations during reverse circulation. Valves shall be pressure tested before each well servicing operation using low-pressure air and high-pressure fluid.
7	Drilling/Completion Operations	604c.(2).K. Pit Level Indicators: All storage tanks used for active drilling operations (used in lieu of pits) contain pit level monitors with Electronic Drilling Recorders (EDR). KMG uses EDRs with pit level monitor(s) and alarm(s) for production rigs. Basic level gauges are used on tanks utilized for the surface rig.
8	Drilling/Completion Operations	604c.(2).L. Drill Stem Tests: No drill stem tests are planned and none will be performed without prior approval from the Director.
9	Drilling/Completion Operations	803. Lighting: To the extent practicable, site lighting shall be shielded and directed downward and inward toward operations to avoid glare on public roads and nearby Building Units.

Total: 9 comment(s)

### Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.  
[http://cogcc.state.co.us/documents/reg/Policies/Wildlife\\_Notice.pdf](http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf)

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.  
<http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf>

### Attachment Check List

<b>Att Doc Num</b>	<b>Name</b>
401657830	FORM 2 SUBMITTED
401689866	OffsetWellEvaluations Data
401689870	EXCEPTION LOC WAIVERS
401689896	EXCEPTION LOC REQUEST
401689901	SURFACE AGRMT/SURETY
401689907	WELL LOCATION PLAT
401689912	DEVIATED DRILLING PLAN

401689916	DIRECTIONAL DATA
401700508	PROPOSED SPACING UNIT
401834260	OFFSET WELL EVALUATION

Total Attach: 10 Files

**General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Per operator, corrected right to construct to O&G lease. Final Review Completed.	11/02/2018
Engineer	Offset wells evaluated.	09/14/2018
Permit	Passed Completeness.	08/02/2018

Total: 3 comment(s)