

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401791051

Receive Date:

11/20/2018

Report taken by:

PETER GINTAUTAS

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Refer to Rules 340, 905, 906, 907, 908, 909, and 910

OPERATOR INFORMATION

Name of Operator: <u>KERR MCGEE OIL & GAS ONSHORE LP</u>	Operator No: <u>47120</u>	Phone Numbers
Address: <u>P O BOX 173779</u>		Phone: <u>(970) 336-3500</u>
City: <u>DENVER</u>	State: <u>CO</u>	Zip: <u>80217-3779</u>
Contact Person: <u>Phil Hamlin</u>	Email: <u>Phil.Hamlin@anadarko.com</u>	Mobile: <u>()</u>

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 9407 Initial Form 27 Document #: 200438326

PURPOSE INFORMATION

- | | |
|--|--|
| <input type="checkbox"/> 901.e. Sensitive Area Determination | <input checked="" type="checkbox"/> 909.c.(5), Rule 910.b.(4): Remediation of impacted ground water |
| <input type="checkbox"/> 909.c.(1), Rule 905: Pit or PW vessel closure | <input type="checkbox"/> Rule 909.e.(2)A.: Notice completion of remediation in accordance with Rule 909.b. |
| <input checked="" type="checkbox"/> 909.c.(2), Rule 906: Spill/Release Remediation | <input type="checkbox"/> Rule 909.e.(2)B.: Closure of remediation project |
| <input type="checkbox"/> 909.c.(3), Rule 907.e.: Land treatment of oily waste | <input type="checkbox"/> Rule 906.c.: Director request |
| <input type="checkbox"/> 909.c.(4), Rule 908.g.: Centralized E&P Waste Management Facility closure | <input type="checkbox"/> Other _____ |

SITE INFORMATION

N Multiple Facilities (in accordance with Rule 909.c.)

Facility Type: <u>SPILL OR RELEASE</u>	Facility ID: <u>443083</u>	API #: _____	County Name: <u>WELD</u>
Facility Name: <u>SPILL/RELEASE POINT</u>		Latitude: <u>40.215889</u>	Longitude: <u>-104.938253</u>
** correct Lat/Long if needed: Latitude: _____		Longitude: _____	
QtrQtr: <u>NWNW</u>	Sec: <u>19</u>	Twp: <u>3N</u>	Range: <u>67W</u>
Meridian: <u>6</u>		Sensitive Area? <u>Yes</u>	

SITE CONDITIONS

General soil type - USCS Classifications CL Most Sensitive Adjacent Land Use Agriculture

Is domestic water well within 1/4 mile? Yes Is surface water within 1/4 mile? No

Is groundwater less than 20 feet below ground surface? Yes

Other Potential Receptors within 1/4 mile

Water well approximately 570 feet (ft) northwest, livestock approximately 1,180 feet north, occupied building approximately 850 ft south, and groundwater approximately 5 ft below ground surface (bgs).

SITE INVESTIGATION PLAN

TYPE OF WASTE:

☒ E&P Waste

☐ Other E&P Waste

☐ Non-E&P Waste

☒ Produced Water

☐ Workover Fluids

☒ Oil

☐ Tank Bottoms

☐ Condensate

☐ Pigging Waste

☐ Drilling Fluids

☐ Rig Wash

☐ Drill Cuttings

☐ Spent Filters

☐ Pit Bottoms

☐ Other (as described by EPA)

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
Yes	GROUNDWATER	See attached data	Groundwater Sampling/Laboratory Analysis
Yes	SOILS	36ft N-S x 30ft E-W x 8.5ft bgs	Soil Sampling/Laboratory Analysis

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

While deconstructing the HSR-Sekich-63N67W/19SWNW location, soil with historical petroleum hydrocarbon impacts was encountered beneath the production tanks. The volume of the release is unknown. The petroleum hydrocarbon impacted soil was excavated.

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

☒ Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Please refer to the Form 27 submitted to the Colorado Oil and Gas Conservation Commission (COGCC) on December 10, 2015.

Proposed Groundwater Sampling

☒ Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Please refer to the Form 27 submitted to the COGCC on December 10, 2015.

Proposed Surface Water Sampling

☐ Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

☐ Additional alternative investigative actions described in attached Site Investigation Plan (summary):

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 7

Number of soil samples exceeding 910-1 2

Was the areal and vertical extent of soil contamination delineated? Yes

Approximate areal extent (square feet) 1110

NA / ND

-- Highest concentration of TPH (mg/kg) 1250

NA Highest concentration of SAR

BTEX > 910-1 Yes

Vertical Extent > 910-1 (in feet) 7

Groundwater

Number of groundwater samples collected 86

Was extent of groundwater contaminated delineated? Yes

Depth to groundwater (below ground surface, in feet) 5'

Number of groundwater monitoring wells installed 15

Number of groundwater samples exceeding 910-1 15

-- Highest concentration of Benzene (µg/l) 3690

-- Highest concentration of Toluene (µg/l) 1960

-- Highest concentration of Ethylbenzene (µg/l) 377

-- Highest concentration of Xylene (µg/l) 4020

NA Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected

Number of surface water samples exceeding 910-1

If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☐ Were background samples collected as part of this site investigation?

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards)

Volume of liquid waste (barrels)

☐ Is further site investigation required?

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Approximately 270 cubic yards of impacted soil were removed from the 2007 excavation and transported to the Kerr-McGee Land Treatment Facility in Weld County, Colorado, for recycling. The impacted soil was excavated into the capillary and phreatic zones to address potential hydrocarbon impacts that may have been present below the groundwater table due to past seasonal fluctuations. The general site layout and excavation footprint are depicted on the Site Map provided as Figure 1.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

While backfilling the excavation, 150 pounds of COGAC®, a carbon-based bioremediation product designed to capture and degrade petroleum hydrocarbons via chemical oxidation and passive bio-stimulation, were applied to the clean backfill in a series of lifts in the capillary and phreatic horizons.

Measurable free product was detected in monitoring well MW02 in September 2016. In November 2017, MW02 was replaced with two-inch monitoring well MW02R. A product skimmer was installed in the well in March 2017 and product recovery events resumed on a bi-monthly schedule. To date, a total of approximately 77.5 gallons of free product mixed with groundwater have been purged from the monitoring well and transferred to a Kerr-McGee produced water sump. The quarterly depth to water and depth to product measurements are summarized in Table 1.

Three fluid recovery wells will be installed at the site, and a series of enhanced fluid recovery events will be conducted to address remaining free product in MW02R.

Soil Remediation Summary

☐ In Situ

Bioremediation (or enhanced bioremediation)

Chemical oxidation

Air sparge / Soil vapor extraction

Natural Attenuation

Other

☒ Ex Situ

Yes Excavate and offsite disposal

If Yes: Estimated Volume (Cubic Yards) 270

Name of Licensed Disposal Facility or COGCC Facility ID # 149007

No Excavate and onsite remediation

Land Treatment

Bioremediation (or enhanced bioremediation)

Chemical oxidation

Other

Groundwater Remediation Summary

Yes Bioremediation (or enhanced bioremediation)

Yes Chemical oxidation

No Air sparge / Soil vapor extraction

Yes Natural Attenuation

Yes Other COGAC® Application and Free Product Removal

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

Since the submittal of the eForm 27 Supplemental submitted to the COGCC on December 28, 2017, two additional temporary monitoring wells (TMW03 and TMW04) were installed at the site to establish points of compliance. The temporary monitoring wells are abandoned annually for the harvest season. Boring logs with well completion diagrams are attached.

Monitoring wells MW01 through MW09 and temporary monitoring wells TMW01 through TMW04 are sampled on a quarterly basis and submitted for laboratory analysis of benzene, toluene, ethylbenzene, and total xylenes (BTEX) by United State Environmental Protection Agency (USEPA) Method 8260C. The monitoring well locations are depicted on Figure 1. A Groundwater Elevation Contour Map generated using the July 2018 survey data is provided as Figure 2. The groundwater analytical results are summarized in Table 1, and the laboratory analytical report for the July 2018 groundwater monitoring event is attached.

Groundwater monitoring will continue on a quarterly basis until a No Further Action status request is warranted.

REMEDIATION PROGRESS UPDATE

PERIODIC REPORTING

Frequency: ☐ Quarterly ☐ Semi-Annually ☒ Annually ☐ Other _____

Report Type: ☒ Groundwater Monitoring ☐ Land Treatment Progress Report ☐ O&M Report
☐ Other _____

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? Yes _____

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

The petroleum hydrocarbon impacted soil was transported to the Kerr-McGee Land Treatment Facility in Weld County, Colorado, for recycling.

Volume of E&P Waste (solid) in cubic yards 270

E&P waste (solid) description Petroleum hydrocarbon impacted soil

COGCC Disposal Facility ID #, if applicable: 149007

Non-COGCC Disposal Facility: _____

Volume of E&P Waste (liquid) in barrels 0

E&P waste (liquid) description _____

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: _____

REMEDIATION COMPLETION REPORT

REMEDIATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No _____

Do all soils meet Table 910-1 standards? No _____

Does the previous reply indicate consideration of background concentrations? _____

Are the only residual soil impacts pH, SAR, or EC at depths greater than 3 feet below ground surface? Yes _____

Does Groundwater meet Table 910-1 standards? No _____

Is additional groundwater monitoring to be conducted? Yes _____

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

The Kerr-McGee facility was deconstructed and restored to its pre-release grade.

Is the described reclamation complete? No _____

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☐ Interim? ☐ Final?

Did the Surface Owner approve the seed mix? _____

If NO, does the seed mix comply with local soil conservation district recommendations? _____

IMPLEMENTATION SCHEDULE

PRIOR DATES

Date of Surface Owner notification/consultation, if required. 08/26/2015

Actual Spill or Release date, if known. 08/26/2015

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). 08/24/2015

Date of commencement of Site Investigation. 08/26/2015

Date of completion of Site Investigation. 02/16/2018

REMEDIAL ACTION DATES

Date of commencement of Remediation. 08/26/2015

Date of completion of Remediation.

SITE RECLAMATION DATES

Date of commencement of Reclamation.

Date of completion of Reclamation.

OPERATOR COMMENT

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Phil Hamlin

Title: Senior HSE Representative

Submit Date: 11/20/2018

Email: Phil.Hamlin@anadarko.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: PETER GINTAUTAS

Date: 11/20/2018

Remediation Project Number: 9407

COA Type

Description

	Submit reports of site investigation and progress of remediation including results of sampling and analysis on an annual basis or more often until remediation is closed.
--	---

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

<u>Att Doc Num</u>	<u>Name</u>
401791051	FORM 27-SUPPLEMENTAL-SUBMITTED
401791060	LOGS
401791338	ANALYTICAL RESULTS
401809257	SITE MAP
401809259	GROUND WATER ELEVATION MAP

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)