

FORM

21

Rev
08/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

401803656

Date Received:

11/08/2018

MECHANICAL INTEGRITY TEST

1. Duration of the pressure test must be a minimum of 15 minutes.
2. An original pressure chart must accompany this report if this test was not witnessed by an OGCC representative.
3. For production wells, test pressures must be at a minimum of 300 psig.
4. New injection wells must be tested to maximum requested injection pressure.
5. For injection wells, test pressures must be at least 300 psig or average injection pressure, whichever is greater.
6. A minimum 300 psi differential pressure must be maintained between the tubing and tubing/casing annulus pressure.
7. Do not use this form if submitting under provisions of Rule 326.a(1)B. or C.
8. Written OGCC notification must be provided 10 days prior to the test via Form 42, Field Operations Notice
9. Packers or bridge plugs, etc., must be set within 100 feet of the perforated interval to be considered a valid test.

Complete the Attachment

Checklist

OP OGCC

OGCC Operator Number: 47120	Contact Name: SABRINA FRANTZ	Pressure Chart		
Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP	Phone: (970) 515-1141	Cement Bond Log		
Address: P O BOX 173779		Tracer Survey		
City: DENVER State: CO Zip: 80217-3779 Email: SABRINA.FRANTZ@ANADARKO		Temperature Survey		
		Inspection Number		
API Number: 05-123-27386	OGCC Facility ID Number: 287126			
Well/Facility Name: FRANK	Well/Facility Number: 9-31			
Location QtrQtr: NESE	Section: 31 Township: 4N Range: 67W Meridian: 6			

☒ SHUT-IN PRODUCTION WELL
 ☐ INJECTION WELL
 Last MIT Date: _____

Test Type:

- ☒ Test to Maintain SI/TA status
 ☐ 5-Year UIC
 ☐ Reset Packer
- ☐ Verification of Repairs
 ☐ Annual UIC TEST
- ☐ Describe Repairs or Other Well Activities: _____

Wellbore Data at Time of Test				Casing Test Use when perforations or open hole is isolated by bridge plug or cement plug; use if cased-hole only with plug back total depth. Bridge Plug or Cement Plug Depth 7224
Injection Producing Zone(s)	Perforated Interval	Open Hole Interval		
CODL	7306 - 7328			
Tubing Casing/Annulus Test				
Tubing Size:	Tubing Depth:	Top Packer Depth:	Multiple Packers?	

Test Data (Use -1 for a vacuum)

Test Date	Well Status During Test	Casing Pressure Before Test	Initial Tubing Pressure	Final Tubing Pressure
09-27-2018	SHUT -IN	0	0	0
Casing Pressure Start Test	Casing Pressure - 5 Min.	Casing Pressure - 10 Min.	Casing Pressure Final Test	Pressure Loss or Gain
377	380	382	384	7

 Test Witnessed by State Representative? ☐ OGCC Field Representative _____

OPERATOR COMMENTS:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed:

Print Name: CHERYL LIGHT

Title: STAFF REGULATORY ANALYST

Email: CHERYL.LIGHT@ANADARKO.COM

Date: 11/8/2018

Based on the information provided herein, this Notice (Form 21) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Daigle, Ryan

Date: 11/26/2018

CONDITIONS OF APPROVAL, IF ANY:

Attachment Check List

Att Doc Num

Name

401803656	FORM 21 SUBMITTED
401803701	FORM 21 ORIGINAL
401803705	PRESSURE CHART

Total Attach: 3 Files

General Comments

User Group

Comment

Comment Date

Engineer	Operator was notified to include a data table with all pressure charts per the guidance. Field staff was contacted, packer is within the permissible distance from the perforated interval portion of the wellbore, chart is included, pressure remained within acceptable parameters.	11/26/2018
----------	--	------------

Total: 1 comment(s)