



00277824

#COPY#

Budget Bureau 42-R358.2.
Approval expires 12-31-82.

(SUBMIT IN TRIPLICATE)

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEYBEST IMAGE
AVAILABLEDenver
Land Office _____
Lease No. 033749-1
Unit 1

SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL	SUBSEQUENT REPORT OF WATER SHUT-OFF
NOTICE OF INTENTION TO CHANGE PLANS	SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING
NOTICE OF INTENTION TO TEST WATER SHUT-OFF	SUBSEQUENT REPORT OF ALTERING CASING
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL	SUBSEQUENT REPORT OF REDRILLING OR REPAIR
NOTICE OF INTENTION TO SHOOT OR ACIDIZE	SUBSEQUENT REPORT OF ABANDONMENT
NOTICE OF INTENTION TO PULL OR ALTER CASING	SUPPLEMENTARY WELL HISTORY
NOTICE OF INTENTION TO ABANDON WELL	
Running & cementing 9 1/2" casing	134

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

B. W. Hesser Well #2

December 15

19 51

Well No. 2 is located 1900 ft. from {N} line and 330 ft. from {E} line of sec. 4

10156 sec. 4	128	974	624
(1/4 Sec. and Sec. No.)	(Twp.)	(Range)	(Meridian)
Pariahs	Jeff	Colorado	
(Field)	(County or Subdivision)	(State or Territory)	

The elevation of the derrick floor above sea level is 6745 ft.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

Run 131 joints and 1 piece of 9 1/2" OD 20# 1-3/8 extreme line regular Spring
seamless casing as follows:131 joints and 1 pc. casing
1 Baker float guide shoe

5144.84' net	5195.34' gross
2.46	2.46
5146.30' net	5196.80' gross

Landed at 5156.04', 11.30' below Kelly bushing in slips in a Cameron landing
flange. Cemented with 215 sac OK silo-set cement. Displaced cement with 114 barrels
mud, using rig pump. Plug bumped at 1000 psi. Cementing was done by Halliburton
Oil Well Cementing Company.Pressure tested casing to 2000 psi for one hour; no leaks or drops in pressure
were noted.

I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company Mountain Fuel Supply Company

Address P. O. Box 1129

Rock Springs, Wyoming

By D. K. Bowen

Title Manager, Producing Division