

FORM  
2

Rev  
08/16

## State of Colorado

### Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401793768

Date Received:

10/18/2018

#### APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Anschutz Equus Farms

Well Number: 5-61-35-4956B

Name of Operator: HIGHPOINT OPERATING CORPORATION

COGCC Operator Number: 10071

Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

Contact Name: Delores Montoya

Phone: (303)312-8145

Fax: ( )

Email: dmontoya@hpres.com

#### RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20040060

#### WELL LOCATION INFORMATION

QtrQtr: NESE Sec: 34 Twp: 5N Rng: 61W Meridian: 6

Latitude: 40.354739

Longitude: -104.186824

Footage at Surface: 1686 Feet FNL/FSL FSL 360 Feet FEL/FWL FEL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4481

County: WELD

GPS Data:

Date of Measurement: 09/17/2018 PDOP Reading: 1.4 Instrument Operator's Name: JAMES FRESHWATER, N.W.

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FSL 1103 FSL 460 FWL 1102 FSL 400 FEL  
Sec: 35 Twp: 5N Rng: 61W Sec: 36 Twp: 5N Rng: 61W

#### LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.  
(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Please view Lease Map in green.

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 3797 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 5280 Feet

Above Ground Utility: 703 Feet

Railroad: 5280 Feet

Property Line: 360 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 612 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-1124	1280	Sec. 35 & 36 ALL

## DRILLING PROGRAM

Proposed Total Measured Depth: 16016 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: \_\_\_\_\_ Feet ☒ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Land application

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: 454282 or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36	0	930	470	930	0
1ST	8+3/4	7	26	0	6277	658	6277	600
1ST LINER	6+1/8	4+1/2	11.6	5374	16016	540	16016	5374

☒ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

The Anschutz Equus Farms Fed 5-61-35-4956B well has a bottom-hole location beyond the unit boundary setback. The bottom of the completed interval will be within the unit boundary setback at 1102' FSL and 460' FEL of Section 36. The wellbore beyond the unit boundary setback will be physically isolated and will not be completed.

The distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed within the unit was measured to the Anschutz Equus Farms Fed 5-61-35-6457B, this distance was measured in 3D.

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ No \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: 458008

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes \_\_\_\_\_

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Delores Montoya

Title: Sr. Regulatory Analyst Date: 10/18/2018 Email: dmontoya@hpres.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: 12/20/2018

Expiration Date: 12/19/2020

API NUMBER

05 123 49227 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### COA Type

### Description

	Operator will ensure the wellbore beyond the unit boundary setback is physically isolated and is not completed. In the Operator Comments on the Form 5A the operator will (1) report the footages from the section lines of the bottom of the completed interval (2) describe how the wellbore beyond the unit boundary setback is physically isolated and (3) certify that none of the wellbore beyond the setback was completed.
	Bradenhead tests shall be performed and reported according to the following schedule and Form 17 submitted within 10 days of each test.: 1) All: Within 60 days of rig release, prior to stimulation. 2) Delayed completion: 6 months after rig release, prior to stimulation. 3) All: Within 90 days after first sales, as reported on the Form 5A, Completed Interval Report.
	1) Submit Form 42 online to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Provide cement coverage to a minimum of 200' above Niobrara. Verify coverage with cement bond log.

## Best Management Practices

### No BMP/COA Type

### Description

1	Drilling/Completion Operations	HighPoint will adhere to the COGCC Policy for Bradenhead Monitoring effective 5/29/12.
2	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.
3	Drilling/Completion Operations	Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores, prior to drilling operations for the proposed well.

Total: 3 comment(s)

## Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.  
[http://cogcc.state.co.us/documents/reg/Policies/Wildlife\\_Notice.pdf](http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf)

## Attachment Check List

### Att Doc Num

### Name

401793768	FORM 2 SUBMITTED
401799893	OffsetWellEvaluations Data
401799897	DIRECTIONAL DATA
401799898	WELL LOCATION PLAT
401799904	DEVIATED DRILLING PLAN

401799921	MINERAL LEASE MAP
401799924	WASTE MANAGEMENT PLAN
401799932	EXCEPTION LOC REQUEST
401799935	EXCEPTION LOC WAIVERS
401802368	SURFACE AGRMT/SURETY
401883440	OFFSET WELL EVALUATION

Total Attach: 11 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Permitting review complete, passed Final Review.	12/12/2018
Permit	Corrected operator comment for drilling beyond the setback to say 460' FEL. Distance from Completed Portion of Wellbore to Nearest Unit Boundary corrected to 460 ft. Added Location ID 458008 to reflect 2A, doc #401794068. Emailed the State Land Board (SLB) for confirmation of State Land Board consent.  No objection was received from the State Land Board (SLB).	12/11/2018
Engineer	Increased surface casing to 930' based on WW depths (<1 mile: 910', Receipt=3667195, Permit=0296759, gs 4520'). Increased cement quantity proportionally.	11/27/2018
Engineer	Evaluated existing wells within 1500' of proposed directional.	11/27/2018
Permit	Added the anti-collision BMP as per operators Passed Completeness	10/31/2018
Permit	Form is missing anti-collision BMP/COA, waiting on operator's response	10/27/2018
Permit	Corrected Well Name to Anschutz Equus Farms per operator request.	10/24/2018

Total: 7 comment(s)