

# DUCO INCORPORATED

Well Servicing Company

2403 1/2 E. Main - PO Box 416 (mailing)

Rangely, CO 81648

Phone (970-629-2614 or (970)-675-8685

## cement work order

DATE:

jan 29 2018

INVOICE #

CO012918C

### COMMENTS

Rig crew helped hook up lines and with operation of pumping the cement bough pizza and drinks for them.\

Hiring Company: hayes

Address:

City, ST, ZIP:

API:05-103-07181 Rio Mesa Resources Inc

lease #46246

well:Hill Carry and Don #7

Rig: hayes

Date: jan 29,2018

State/County: Colorado. Rio Blanco

Range/Township:

Operator: B. Rector

Toolpusher:

Cement Hand:

Floor Hand:

Floor Hand:

Company Foreman:

Signature:

Hour Work Started:8:00A.M

Hour Work Completed:

BREAKDOWN OF CHARGES	HOURS/QTY.	RATE	AMOUNT
Rig and 3 man crew		\$260.00	
Full Time Supervisor (per day)	1.00	\$500.00	500.00
Travel Time	1.00	\$220.00	220.00
pickup	1.00	\$100.00	100.00
Cement Truck	1.00	\$1,400.00	1,400.00
Pump and Tank		\$620.00	
Blower	1.00	\$200.00	200.00
Flat Tank (per day)	0.00	\$75.00	
Back Hoe and welder		\$50.00	
Crew Sub. Pay (per day X no. of men)		\$130.00	
pod trailer	1.00	\$400.00	400.00
Additional Labor. Cement	68.00	\$35.00	2,380.00
Travel For TBG		\$65.00	

### DESCRIPTION OF WORK PERFORMED:

Drove from yard at 7:30A.M RU green cement truck pod trailer and blower mounted to trailer, started pumping cement 15.8LBS class G at 8:00A.M (50)SKS. Displaced with 2.9BBLS EOT 902 Displaced with 750 to set 150 ft balance plug. Wait four hours for cement to dry go in and hard tag with TBG. went to tag cement could not find pumped class g 15.8LBS cement at 902ft with 2% cal pumped a 50ft plug displacing with 3BBLS cleaned up winterized pump, done for the day

SUBTOTAL

TAX RATE

0.00%

SALES TAX

OTHER

TOTAL

\$5,025.00

5200.00

Make all checks payable to: **Duco Inc.**

All accounts net 30 days. 24% per annum interest plus cost of attorney's fees and collection fees

THANK YOU FOR YOUR BUSINESS!

# DUCO INCORPORATED

Well Servicing Company  
2403 1/2 E. Main - PO Box 416 (mailing)  
Rangely, CO 81648  
Phone (970)-629-2614 or (970)-675-8685


## cement work order

DATE: Jan 30 2018  
INVOICE # CO013018C

Hiring Company: hayes  
Address:  
City, ST, ZIP:  
API:05-103-07181 Rio Mesa Resources inc  
lease #46246  
well:Hill Carry and Don #7  
Rig: hayes  
Date: Jan 30,2018  
State/County: Colorado. Rio Blanco  
Range/Township:

Operator: B. Rector  
Toolpusher:  
Cement Hand:  
Floor Hand:  
Floor Hand:

Company Foreman:  
Signature:



### COMMENTS

green truck working good  
fixed coolant leak grease  
whole truck.

Hour Work Started:8:00A.M  
Hour Work Completed:

BREAKDOWN OF CHARGES	HOURS/QTY.	RATE	AMOUNT
Rig and 3 man crew		\$260.00	
Full Time Supervisor (per day)	1.00	\$500.00	500.00
Travel Time	0.00	\$220.00	
pickup	1.00	\$100.00	100.00
Cement Truck	1.00	\$1,400.00	1,400.00
Pump and Tank		\$620.00	
Blower	1.00	\$200.00	200.00
Flat Tank (per day)	0.00	\$75.00	
Back Hoe and welder		\$50.00	
Crew Sub. Pay (per day X no. of men)		\$130.00	
pod trailer	1.00	\$400.00	400.00
Additional Labor. Cement	45.00	\$35.00	1,575.00
Travel For TBG		\$65.00	
SUBTOTAL			
TAX RATE			0.00%
SALES TAX			-
OTHER			
TOTAL			\$4,175.00

### DESCRIPTION OF WORK PERFORMED:

start equipment warm up start pumping cement at 8:00A.M (45)SKS of class g 15.8 LBS at 120 ft end of TBG putting a 125 plug down hole bring cement to surface, R/D dig up well head cut off well head four ft below surface top cap, weld on sign take picture and gps location for BLM back fill move back to yard.

Make all checks payable to: **Duco Inc.**

All accounts net 30 days. 24% per annum interest plus cost of attorney's fees and collection fees

THANK YOU FOR YOUR BUSINESS!