

**Bonanza Creek Energy Operating, Inc.**  
**Daily Completion/Workover Report**

New Drill     Recompletion     LOE     Re-Frac     Casing Repair     P&A  
 Date: 18-Sep-08    Well Name: Guttersen 12-9    AFE: 8501

Legal Desc: SWNW    Sec: 9    Twn: 4N    Rng: 63W

Zone	Perforations	Surface Csg:	19 jts	Size: <u>8 5/8"</u>	Wt/Gd: <u>24#</u>	Conn. <u>ST&amp;C 8rd</u>	Depth: <u>833'</u>
Codell	6638' - 6650' ( 48 holes )	Production Csg:	183 jts	Size: <u>4 1/2"</u>	Wt/Gd: <u>11.6# N-80</u>	Conn. <u>LT&amp;C 8rd</u>	Depth: <u>7221'</u>
		Tubing:		Size: _____	Wt/Gd: _____	Top: _____	Depth: _____
		Tubing:	215 jts	Size: <u>2 3/8"</u>	Wt/Gd: <u>4.7# J-55</u>	Conn. <u>EUE 8rd</u>	Depth: <u>7064'</u>
		Packer:		RBP: _____	CIBP: _____	Sd Plug: _____	Last Cleaned Out To <u>7176'</u>
<b>CIFP</b>	<b>7030'</b>	TD	<u>7237'</u>	PBTD <u>7190'</u>	TOC _____	3080' - 5970'	
J-Sand	7086' - 7094' ( 32 holes )	Fluid Lost	_____	Recovered	_____	Load Remaining _____	

Other Information: \_\_\_\_\_

Job Objective: Codell / Niobrara Completion

**Operation Past 24 Hours**

9-18-08  
 IWP-150/0  
 RU and blow tbg down to the prod tank then RU and work scrapper through the plug set area above the J-sand perms. RU and lay 215 jts of tbg down on seals. RU JW Wireline to set Halliburton 4 1/2" 10K EZ-Drill cast iron flow through frac plug above the J-sand perms at **7030'**. Plug is set **56'** above the top J-perf at **7086'**. RU B&J Hot Oil and load the csg to test plug to 5000 psi. Csg loaded w/ 82 bbls and tested good to 5000 psi for 15 min w/ no leak off. RD Hot Oiler then RU JW Wireline to perforate the Codell. Tie into formation and correlate w/ open hole logs dated 9/15/07 and CBL dated 10/2/07, perforate Codell formation from **6638'** to **6650'**, w/ 3 1/8" slick gun, 4/spf, 48 holes, all shots fired. RD wireline and ECWS. Clean up location and move rig off. Work to set frac tanks and load for Monday 9/22/08 frac date.

Proposed Operations: Set and fill frac tanks

Contractor: B&J / STS / HES / JW / Integrity / ECWS / K&J    Supervisor: Kurt Dodge

**Cost Estimate**

Intangible	Description	Daily	Cum	Tangible	Daily	Cum
Welding				Production Liner		
Misc. Pump	B&J			Production Casing		
Trucking	Integrity			Tubing		
Bits				Tree		
Drilling Fluids				Pumping Unit & Engine		
Cement & Services				Subsurface Equipment		
Cased Hole Logging & Perf	JW / HES			Flow Line & Connections		
Equipment Rentals	STS			Separation/Treating Equip		
Contract Services				Storage Tanks		
Completion Unit	ECWS			Wellhead Equipment		
Swab Rig				Other Lease Equipment		
Stimulation						
Hydrotesting						
Professional Services	K&J					
Roustabout						
Frac tanks / KCL water						
Slickline						
Anchors						
Tubing rental						
	<b>Total Intangibles</b>			<b>Total Tangible</b>		
				<b>Completion Cost</b>		
				<b>Drill Cost</b>		
				<b>Total Cost</b>		