

Foundation Energy Management, LLC

WELLBORE DIAGRAM

Well / Battery	Prospect Name		Total Depth	Current Status
Fed Plover 28-5X	DOC - Fund 4		7100	SI
Location	Sec-Twn-Rng		Producing Horizon	County & State
SWNW	28-8N-60W		DSND	Weld, CO

WELLBORE DIAGRAM

Prepared Date: 11/16/2018

Prepared By: Adam Johnson

General Info

API #: 05-123-20126

KB Elevation: 4,961'

GL Elevation: 4,973'

Spud Date: 09-10-2010

Completion Date: 09-16-2010

TVD: 7083

MD: 7083

Last PBDT: 7,070' (10-12-2017)

Tubing Detail

2-3/8" inch(OD)

4.7 # (weight)

J-55 grade

Tubing Tally

	Length	Depth
207 jts - 2-3/8" tbg	6886	6886
SN	1	6887
Packer	5	6892

Surface Casing

8-5/8" inch (OD)

24 # (weight)

grade

525 depth from KB

Surface cement top

365 sacks of cement

12.25 inch (OD) HOLE SIZE

Visual Returns

Rod Design

length

depth

no rods

Production Casing

5-1/2" inch (OD)

17.00 # (weight)

grade

7083 depth from KB

5893 cement top

190 sacks of cement

7-7/8" inch (OD) HOLE SIZE

CBL

Open Perforations

6,914' - 6,924'

DSND

Pump Details:

Pumping Unit Details:

N/A

Well Notes: