

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



00270493

(Indicate nature of data by checking below)

336-3

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report _____
 Report of setting Production casing _____ **XX**

Following is a ~~(notice of intention to do work)~~ Nov. 24 19 52
 (report of work done) (On land)
 (patented) described as follows:

<u>Colorado</u>	<u>Logan</u>	<u>Mt Hope</u>
State	County	Field
<u>15</u>	<u>10-26</u>	
<u>C. F. Green A</u>	<u>24</u>	<u>SW 1/4</u>
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)
		<u>9N</u>
		<u>54W</u>
		<u>6PM</u>
		(Range) (Meridian)

The well is located 1000 ft. (N) of South Line and 368 ft. (E) of _____
 (S) (W)
East Line SW 1/4 Sec. 24

The elevation above sea level is 4239.0 KB
4226.2 ft. sur.

Details of Plan of Work: (State names of and expected depths to objective sands:
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
 ing points, and all other important proposed work.)

On Oct. 31, 1952 7" OD 20 & 23# casing was run and cemented at
 a depth of 5100' KB with 170 sacks reg cement with 2% gel. The hole was
 drilled to a total depth of 5140'. A description of the casing run is as
 follows: 7" OD 23# (27jts) 838', 7" OD 20# (137jts) 4311' J-55 ST&C casing
 Scratchers were placed 5096'-5040' and 4970'-4937'. Centrizers were placed
 5096', 5040', 4970' 4935'. The cement was allowed to set 48 hours after drill-
 ing out cement the casing was tested with 500 psi for 30 minutes finding no
 leaks. Work was continued.

Approved: DEC 1 1952

 Director

Company The Texas Company-Producing Det
 Address Box 1346 Casper, Wyoming
 By Walter Rand
 Title District Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.

OGCC(2) TTF WR MME